

**THE
UNIVERSITY
OF RHODE ISLAND**

DIVISION OF
ADMINISTRATION
AND FINANCE

THINK BIG WE DO™



PURCHASING DEPARTMENT
210 Flagg Road, Kingston, RI 02881 USA p: 401.874.2171 f: 401.874.2306 uri.edu/strategic-procurement/purchasing

BID/PROPOSAL

COMMODITY: CONSTRUCTION OF NEW 400' RADIO TOWER & TRANSMITTER BLDG. DATE: 1/2/25

FORMAL BID NO. _____ PUBLIC BID NO. 101448

BIDS ARE TO BE RECEIVED IN URI PURCHASING DEPARTMENT BY: DATE: 1/30/25 TIME: 2:00 PM
Eastern Time

BUYER: Andrea Boucher Digitally signed by Andrea Boucher
Date: 2025.01.02 08:51:40 -0500 rlc SURETY REQUIRED: YES: X NO: _____

PRE-BID/PROPOSAL CONFERENCE: DATE: 1/10/25 TIME: 11:00 AM

MANDATORY: YES: _____ NO: X

LOCATION: 210 FLAGG RD., 1ST FL. LARGE CONFERENCE RM.
KINGSTON, RI 02881

Questions concerning this solicitation must be received by: DATE: 1/13/25 TIME: 12:00 PM

Questions are to be submitted in a *Microsoft Word* document to: URIPurchasing@uri.edu

Please reference the Bid Number on all correspondence. Questions received, if any, will be posted on the Internet as an addendum to the bid. It is the responsibility of all interested parties to download this information.

For Bid Solicitation Information visit: <http://web.uri.edu/purchasing/bid-information/>

STATEMENT REGARDING COVID-19

Effective immediately, we are suspending all in-person public bid openings until further notice
Public Bid responses will be publicly read via Webex video conferencing. To participate in the bid opening, please visit the following site at the scheduled bid opening date and time:

* URL: <https://rhody.webex.com/meet/uripurchasing>

No offer will be considered that is not accompanied by the attached University of Rhode Island Bidder Certification Form/Contract Offer completed and signed by the offeror.

COMPANY NAME: NORTHEAST TOWERS, INC.

STREET AND NUMBER: 199 BRUCKGARD ROAD

CITY, STATE & ZIP CODE: FARMINGTON CT 06032

Print Name and Title: STEPHEN SAVINO III, Project Manager Telephone Number/Facsimile Number: 860-677-1919 / 860-677-1300

Signature: [Signature] Date: 2/6/2025 E-mail address: SS3@NORTHEASTTOWERS.COM

THIS BID WILL NOT BE HONORED UNLESS SIGNED

SECTION 2 – DISCLOSURES

ALL CONTRACT AWARDS ARE SUBJECT TO THE FOLLOWING DISCLOSURES & CERTIFICATIONS

Offerors must respond to every disclosure statement. A person authorized to enter into contracts must sign the offer and attest to the accuracy of all statements.

Indicate Yes (Y) or No (N):

N 1 State whether your company, or any owner, stockholder, officer, director, member, partner, or principal thereof, or any subsidiary or affiliated company, has been subject to suspension or debarment by any federal, state, or municipal government agency, or the subject of criminal prosecution, or convicted of a criminal offense with the previous five (5) years. If Yes, then provide details below.

N 2 State whether your company, or any owner, stockholder, officer, director, member, partner, or principal thereof, or any subsidiary or affiliated company, has had any contracts with a federal, state or municipal government agency terminated for any reason within the previous five (5) years. If Yes, then provide details below.

N 3 State whether your company or any owner, stockholder, officer, director, member, partner, or principal thereof, or any subsidiary or affiliated company, has been fined more than \$5000 for violation(s) of Rhode Island environmental laws by the Rhode Island Department of Environmental Management within the previous five (5) years. If Yes, then provide details below.

N 4 State whether any officer, director, manager, stockholder, member, partner, or other owner or principal of the Bidder is serving or has served within the past two calendar years as either an appointed or elected official of any state governmental authority or quasi-public corporation, including without limitation, any entity created as a legislative body or public or state agency by the general assembly or constitution of this state. If Yes, then provide details below.

IF YOU HAVE ANSWERED "YES" TO QUESTIONS #1 – 4 PROVIDE DETAILS/EXPLANATION IN AN ATTACHED STATEMENT. INCOMPLETE CERTIFICATION FORMS SHALL BE GROUNDS FOR DISQUALIFICATION OF OFFER.

SECTION 3 - OWNERSHIP DISCLOSURE

Vendors must provide all relevant information. Bid proposals submitted without a complete response may be deemed nonresponsive.

If the vendor is privately held, the vendor shall provide ownership information below.

List each officer, director, manager, stockholder, member, partner, or other owner or principle of the Bidder, and each intermediate parent company and the ultimate parent company of the Bidder. For each individual, provide his or her name, business address, principal occupation, position with the Vendor, and the percentage of ownership, if any, he or she holds in the Vendor, and each intermediate parent company and the ultimate parent company of the Vendor.

If the company is publicly held, the vendor may provide owner information about only those stockholders, members, partners, or other owners that hold at least 10% of the record or beneficial equity interests of the vendor; otherwise, complete ownership disclosure is required.

Stephen Savino OR 100% owner Corp registered in CT, President

Libri Savino Vice President

Vincent Murphy, Secretary/Treasurer

SECTION 4 - CERTIFICATIONS

Bidders must respond to every statement. Bid proposals submitted without a complete response may be deemed nonresponsive.

Indicate "Y" (Yes) or "N" (No), and if "No," provide details below.

THE VENDOR CERTIFIES THAT:

Y 1 I/we certify that I/we will immediately disclose, in writing, to the University Purchasing Agent any potential conflict of interest which may occur during the course of the engagement authorized pursuant to this contract.

Y 2 I/we acknowledge that, in accordance with (1) Chapter §37-2-54(c) of the Rhode Island General Laws "no purchase or contract shall be binding on the state or any agency thereof unless approved by the Department [of Administration] or made under general regulations which the Chief Purchasing Officer may prescribe," and (2) RIGL section §37-2-7(16) which identifies the URI Board of Trustees as a public agency and gives binding contractual authority to the University Purchasing Agent, including change orders and other types of contracts and under State Purchasing Regulation 8.2.B any alleged oral agreement or arrangements made by a bidder or contractor with any agency or an employee of the University of Rhode Island may be disregarded and shall not be binding on the University of Rhode Island.

Y 3 I/we certify that I or my/our firm possesses all licenses required by Federal and State laws and regulations as they pertain to the requirements of the solicitation and offer made herein and shall maintain such required license(s) during the entire course of the contract resulting from the offer contained herein and, should my/our license lapse or be suspended, I/we shall immediately inform the University of Rhode Island Purchasing Agent in writing of such circumstance.

Y 4 I/we certify that I/we will maintain required insurance during the entire course of the contract resulting from the offer contained herein and, should my/our insurance lapse or be suspended, I/we shall immediately inform the University of Rhode Island Purchasing Agent in writing of such circumstance.

Y 5 I/we certify that I/we understand that falsification of any information herein or failure to notify the University of Rhode Island Purchasing Agent as certified herein may be grounds for suspension, debarment and/or prosecution for fraud.

Y 6 I/we acknowledge that the provisions and procedures set forth in this form apply to any contract arising from this offer.

Y 7 I/we acknowledge that I/we understand the State's Purchasing Laws (§37-2 of the General Laws of Rhode Island) and the URI Board of Trustees Regulations apply as the governing conditions for any contract or purchase order I/we may receive from the University of Rhode Island, including the offer contained herein.

Y 8 I/we certify that the bidder: (i) is not identified on the General Treasurer's list, created pursuant to R.I. Gen. Laws § 37-2.5-3, as a person of entity engaging in investment activities in Iran described in § 37-2.5-2(b); and (ii) is not engaging in any such investment activities in Iran.

N 9 If the product is subject to Department of Commerce Export Administration Regulations (EAR) or International Traffic in Arms Regulations (ITAR), please provide the Export Control Classification Number (ECCN) or the US Munitions List (USML) Category: _____

Y 10 I/we certify that the above information is correct and complete.

IF YOU ARE UNABLE TO CERTIFY YES TO QUESTIONS #1 – 8 and 10 OF THE FOREGOING, PROVIDE DETAILS/EXPLANATION IN AN ATTACHED STATEMENT. INCOMPLETE CERTIFICATION FORMS SHALL BE GROUNDS FOR DISQUALIFICATION OF OFFER.

Signature below commits vendor to the attached offer and certifies (1) that the offer has taken into account all solicitation amendments where applicable, (2) that the above statements and information are accurate and that vendor understands and has complied with the requirements set forth herein.

Vendor/Company Name: Northeast Towers, Inc.
Vendor's Signature: [Signature] Bid Number: 101448 Date: 2/6/2025
(Person Authorized to enter into contracts; signature must be in ink) (if applicable)
STEPHEN SAUND III, Project Manager
Print Name and Title of Company official signing offer

Solicitation #: 101448

Solicitation Title: CONSTRUCTION OF NEW 400' RADIO TOWER & TRANSMITTER BLDG.

BID FORM

To: University of Rhode Island, Purchasing Department
210 Flagg Road, Kingston, RI 02881

Project: University of Rhode Island Radio Tower Replacement
Project Number: KC.U.RTOW.2022.001

Bidder:

Northeast Towers, Inc.
Legal name of entity

199 Brickyard Road, Farmington, CT 06032
Address

Stephen Savino III SSavino03@NortheastTowers.com
Contact name Contact email

860.965.1919 860-677-1300
Contact telephone Contact fax

1. BASE BID PRICE

The Bidder submits this bid proposal to perform all of the work (including labor and materials) as described in the solicitation for this Base Bid Price, (including the costs for all Allowances, Bonds, and Addenda):

\$ 891,327.70

(Base Bid Price *in figures* printed electronically, typed, or handwritten legibly in ink)

Eight Hundred Ninety-one Thousand, three hundred twenty seven and seventy cent.
(Base Bid Price *in words* electronically, typed, or handwritten legibly in ink)

Solicitation #: 101448
Solicitation Title: CONSTRUCTION OF NEW 400' RADIO TOWER & TRANSMITTER BLDG.

• **ALLOWANCES**

The Base Bid Price includes the costs for the following Allowances as defined in Specification Section 01 2000:

| | |
|--|---------------------|
| 1. ALLOWANCE #1 | <u>\$130,000.00</u> |
| RF Equipment including antennas, cables, equipment racks, etc. | |
| 2. ALLOWANCE #2 | <u>\$50,000.00</u> |
| Additional site work and tree clearing | |
| Total Allowances: | <u>\$180,000.00</u> |

• **BONDS**

The Base Bid Price includes the costs for all Bid and Payment and Performance Bonds required by the solicitation.

• **ADDENDA**

The Bidder has examined the entire solicitation (including the following Addenda), and the Base Bid Price includes the costs of any modifications required by the Addenda.

All Addenda must be acknowledged.

Addendum No. 1, dated 2/4/25
Addendum No. 2, dated 2/4/25
Addendum No. 3, dated 2/4/25

2. **ALTERNATES N/A**
(Amount in words electronically, typed, or handwritten legibly in ink)

3. **UNIT PRICES N/A**

4. **CONTRACT TIME**

The Bidder offers to perform the work in accordance with the timeline specified below:

- Start of ConstructionApril 1, 2025
- Substantial CompletionSeptember 30, 2025
- Final CompletionOctober 31, 2025

The Final Completion date for Work shall be within **165** calendar days of the Purchase Order from the Division of Purchases.

5. **LIQUIDATED DAMAGES**

Solicitation #: 101448

Solicitation Title: CONSTRUCTION OF NEW 400' RADIO TOWER & TRANSMITTER BLDG.

The successful bidder awarded a contract pursuant to this solicitation shall be liable for and pay the State, as liquidated damages and not as a penalty, the following amount for each calendar day of delay beyond the date for substantial completion, as determined in the sole discretion of the State: Five Hundred Dollars (\$500.00) per day.

BID FORM SIGNATURE(S)

This bid proposal is irrevocable for 60 days from the bid proposal submission deadline.

If the Bidder is determined to be the successful bidder pursuant to this solicitation, the bidder will promptly: (i) comply with each of the requirements of the Tentative Letter of Award; and (ii) commence and diligently pursue the work upon issuance and receipt of the purchase order from the State and authorization from the user agency.

The person signing below certifies that he or she has been duly authorized to execute and submit this bid proposal on behalf of the Bidder.

Date:

2/6/2025

BIDDER

Northeast Towers, Inc.

Name of Bidder

Signature in ink

STEPHEN SAUVINO III / Project Manager

Printed name and title of person signing on behalf of Bidder

#

Bidder's Contractor Registration Number



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)
2/5/2025

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

| | | | |
|---|--|---|--------------|
| PRODUCER The Magnolia Agency 5 Main St Essex CT 06426 | | CONTACT NAME: Rich Varrato PHONE (A/C, No, Ext): (860) 581-8155 FAX (A/C, No): E-MAIL ADDRESS: rich@magnoliainsagency.com | |
| INSURED Northeast Towers, Inc. 199 Brickyard Road Farmington CT 06032 | | INSURER(S) AFFORDING COVERAGE | |
| | | INSURERA: Admiral Insurance Company | NAIC # 24856 |
| | | INSURERB: America Fire and Casualty Co | 24066 |
| | | INSURERC: Third Coast Insurance Company | 10713 |
| | | INSURERD: Carolina Casualty Insurance Company | 10510 |
| | | INSURERE: Crum & Forster Specialty Insurance Comy | 44520 |
| | | INSURERF: American Casualty Co. of Reading PA | 20427 |

COVERAGES **CERTIFICATE NUMBER: CL24121202436** **REVISION NUMBER:**

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

| INSR LTR | TYPE OF INSURANCE | ADDL INSD | SUBR WVR | POLICY NUMBER | POLICY EFF (MM/DD/YYYY) | POLICY EXP (MM/DD/YYYY) | LIMITS |
|----------|--|-----------|----------|---------------------------------|--------------------------|--------------------------|--|
| A | <input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input type="checkbox"/> POLICY <input checked="" type="checkbox"/> PROJECT <input type="checkbox"/> LOC OTHER: | X | Y | CA000032900-07 | 12/17/2024 | 12/17/2025 | EACH OCCURRENCE \$ 1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 300,000 MED EXP (Any one person) \$ 5,000 PERSONAL & ADV INJURY \$ 1,000,000 GENERAL AGGREGATE \$ 2,000,000 PRODUCTS - COMP/OP AGG \$ 2,000,000 |
| B | <input checked="" type="checkbox"/> AUTOMOBILE LIABILITY <input type="checkbox"/> ANY AUTO <input type="checkbox"/> ALL OWNED AUTOS <input type="checkbox"/> HIRED AUTOS <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> NON-OWNED AUTOS | X | Y | BAW65184764 | 10/1/2024 | 10/1/2025 | COMBINED SINGLE LIMIT (Ea accident) \$ 1,000,000 BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ |
| C | <input checked="" type="checkbox"/> UMBRELLA LIAB <input checked="" type="checkbox"/> OCCUR <input type="checkbox"/> EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE DED RETENTION \$ | X | Y | GXL0000286 05 AEC 9806051-13 | 12/17/2024 12/17/2024 | 12/17/2025 12/17/2025 | EACH OCCURRENCE \$ 10,000,000 AGGREGATE \$ 10,000,000 |
| D | WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below | Y/N | N/A | ENURWC0160045 | 6/3/2024 | 6/3/2025 | <input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$ 1,000,000 E.L. DISEASE - EA EMPLOYEE \$ 1,000,000 E.L. DISEASE - POLICY LIMIT \$ 1,000,000 |
| E | Professional/Pollution | | | PKC-115649 | 9/18/2024 | 9/18/2025 | Pollution Agg/Occurrence \$2,000,000 Prof \$5,000,000 |
| F | Inland Marine | | | 7034587345 | 10/01/2024 | 10/01/2025 | Installation Floater \$1,000,000 Rented \$25,000 |

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)
 State of RI, The University of Rhode Island and the URI Board of Trustees are listed as additional insured.
 Waiver of Subrogation applies in favor of additional insureds.
 30 days' advance notice of cancellation, nonrenewal, or material change in coverage, except for 10 day notice for nonpayment, will be sent to URI, 10 Tootell Rd, Kingston RI 02881

| | |
|--|---|
| CERTIFICATE HOLDER University of Rhode Island 10 Tootell Rd Kingston, RI 02881 | CANCELLATION SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. |
| | AUTHORIZED REPRESENTATIVE Rich Varrato/MISHA |



**RI Department of Labor and Training
Workforce Regulation and Safety Division
Professional Regulation - Prevailing Wage**

General Contractor Apprenticeship Certification Form

This form **MUST** be completed and submitted at the time of bidding and is available on the Department of Labor and Training's Website at www.dlt.ri.gov, under Workforce Regulation and Safety, Prevailing Wage, Publications and Forms.

Bid/RFP Number: 101448
Bid/RFP Title: Construction of new 400' radio tower: transmitter Building.
RIVIP Vendor ID#: N/A
Vendor Name: Northeast Towers Inc.
Address: 199 Backyard Road, Farmington, CT 06032
Telephone: 860.677.1999
Fax: 860.677.1300
E-Mail: Vmurphy@northeasttowers.com
Contact Person and Title: Vincent Murphy

Northeast Towers, Inc. (Company Name & Address) (hereafter "bidder") hereby certifies that bidder meets the general contractor apprenticeship requirements of R. I. Gen. Laws § 37- 13- 3.1 because bidder meets one of the following qualifications (check):

- A. Bidder sponsors a current and duly approved Rhode Island Department of Labor and Training Apprenticeship Program and currently employs at least one apprentice per trade/occupation, who will obtain "on the job training" experience in the apprentice's trade by performing on the contract (attach apprenticeship program standards and apprenticeship agreement);
- B. Bidder sponsors a current and duly registered Rhode Island Department of Labor and Training reciprocal apprenticeship program pursuant to R. I. Gen. Laws § 28-45-16 and currently employs at least one apprentice per trade/occupation, who will obtain "on the job training" experience in the apprentice's trade by performing work on the contract (attach apprenticeship program standards, apprenticeship agreement and Rhode Island Department of Labor and Training Reciprocal Apprenticeship Program Approval);

STATE CONTRACT ADDENDUM
RHODE ISLAND DEPARTMENT OF LABOR AND TRAINING
PREVAILING WAGE REQUIREMENTS
(37-13-1 ET SEQ.)

The prevailing wage requirements are generally set forth in RIGL 37-13-1 et seq. These requirements refer to the prevailing rate of pay for regular, holiday, and overtime wages to be paid to each craftsmen, mechanic, teamster, laborer, or other type of worker performing work on public works projects when state or municipal funds exceed one thousand dollars (\$1,000).

All Prevailing Wage Contractors and Subcontractors are required to:

1. Submit to the Awarding Authority a list of the contractor's subcontractors for any part or all of the prevailing wage work in accordance with RIGL § 37-13-4;
2. Pay all prevailing wage employees at least once per week and in accordance with RIGL §37-13-7 (see Appendix B attached);
3. Post the prevailing wage rate scale and the Department of Labor and Training's prevailing wage poster in a prominent and easily accessible place on the work site in accordance with RIGL §37-13-11; posters may be downloaded at www.dlt.ri.gov/pw/Posters.htm or obtained from the Department of Labor and Training, Center General Complex, 1511 Pontiac Avenue, Cranston, Rhode Island;
4. Access the Department of Labor and Training website, at www.dlt.ri.gov on or before July 1st of each year, until such time as the contract is completed, to ascertain the current prevailing wage rates and the amount of payment or contributions for each covered prevailing wage employee and make any necessary adjustments to the covered employee's prevailing wage rates effective July 1st of each year in compliance with RIGL §37-13-8;
5. Attach a copy of this CONTRACT ADDENDUM and its attachments as a binding obligation to any and all contracts between the contractor and any subcontractors and their assignees for prevailing wage work performed pursuant to this contract;
6. Provide for the payment of overtime for prevailing wage employees who work in excess of eight (8) hours in any one day or forty (40) hours in any one week as provided by RIGL §37-13-10;

7. Maintain accurate prevailing wage employee payroll records on a Rhode Island Certified Weekly Payroll form available for download at www.dlt.ri.gov/pw.forms/htm, as required by RIGL §37-13-13, and make those records available to the Department of Labor and Training upon request;
8. Furnish the fully executed RI Certified Weekly Payroll Form to the awarding authority on a monthly basis for all work completed in the preceding month.
9. For general or primary contracts one million dollars (\$1,000,000) or more, shall maintain on the work site a fully executed RI Certified Prevailing Wage Daily Log listing the contractor's employees employed each day on the public works site; the RI Certified Prevailing Wage Daily Log shall be available for inspection on the public works site at all times; this rule shall not apply to road, highway, or bridge public works projects. Where applicable, furnish both the Rhode Island Certified Prevailing Wage Daily Log together with the Rhode Island Weekly Certified Payroll to the awarding authority.
10. Assure that all covered prevailing wage employees on construction projects with a total project cost of one hundred thousand dollars (\$100,000) or more has a OSHA ten (10) hour construction safety certification in compliance with RIGL § 37-23-1;
11. Employ apprentices for the performance of the awarded contract when the contract is valued at one million dollars (\$1,000,000) or more, and comply with the apprentice to journey person ratio for each trade approved by the apprenticeship council of the Department of Labor and Training in compliance with RIGL §37-13-3.1;
12. Assure that all prevailing wage employees who perform work which requires a Rhode Island trade license possess the appropriate Rhode Island trade license in compliance with Rhode Island law; and
13. Comply with all applicable provisions of RIGL §37-13-1, et. seq;

Any questions or concerns regarding this CONTRACT ADDENDUM should be addressed to the contractor or subcontractor's attorney. Additional Prevailing Wage information may be obtained from the Department of Labor and Training at www.dlt.ri.gov/pw.

CERTIFICATION

I hereby certify that I have reviewed this CONTRACT ADDENDUM and understand my obligations as stated above.

Nonrest Towers, Inc

By: V. W. [Signature]
Title: Finance Director

Subscribed and sworn before me this 5th day of Feb, 2025

[Signature]
Notary Public
My commission expires: 12/31/2026



**STATE OF RHODE ISLAND
CONTRACTORS' REGISTRATION AND LICENSING
BOARD**



560 Jefferson Blvd. Warwick, RI 02886

BE IT KNOWN THAT

STEPHEN SAVINO III

of **NORTHEAST TOWERS, INC.**

has met the requirements of the law and has been granted this certificate of registration as a

Commercial Contractor

IN THE STATE OF RHODE ISLAND

Registration Number

GC-47753

Issue Date

August 19, 2024

Expiration Date

September 14, 2025

James Camblo
Building Code Commissioner



Thomas E. Furey, Chair
Contractors' Registration and Licensing Board

Document A310™ - 2010

Conforms with The American Institute of Architects AIA Document 310

Bid Bond

CONTRACTOR:

(Name, legal status and address)

Northeast Towers, Inc.
199 Brickyard Road
Farmington, CT 06032

OWNER:

(Name, legal status and address)

University of Rhode Island
210 Flagg Road
Kingstown, RI 02881

SURETY:

(Name, legal status and principal place of business)

Travelers Casualty and Surety Company of America
One Tower Square
Hartford, CT 06183
Mailing Address for Notices

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

BOND AMOUNT: 5%

Five Percent of Amount Bid

PROJECT:

(Name, location or address, and Project number, if any)

University of Rhode Island Radio Tower Replacement - Project No. KC.U.RTOW.2022.001

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When no such requirement is furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

Signed and sealed this 7th day of February, 2025.

Jain Grego
(Witness)

[Signature]
(Witness)

Northeast Towers, Inc.

(Principal)

(Seal)

By: [Signature]

(Title) PROJECT MANAGER

Travelers Casualty and Surety Company of America

(Surety)

(Seal)

By: Wendy Krystopa

(Title) Wendy Krystopa, Attorney-in-Fact





**Travelers Casualty and Surety Company of America
 Travelers Casualty and Surety Company
 St. Paul Fire and Marine Insurance Company
 Farmington Casualty Company**

POWER OF ATTORNEY

Travelers Casualty and Surety Company of America, Travelers Casualty and Surety Company, St. Paul Fire and Marine Insurance Company, and Farmington Casualty Company are corporations duly organized under the laws of the State of Connecticut (herein collectively called the "Companies"), and the Companies do hereby make, constitute and appoint Wendy Krystopa of Glastonbury, CT, their true and lawful Attorney(s)-in-Fact to sign, execute, seal and acknowledge any and all bonds, recognizances, conditional undertakings and other writings obligatory in the nature thereof on behalf of the Companies in their business of guaranteeing the fidelity of persons, guaranteeing the performance of contracts and executing or guaranteeing bonds and undertakings required or permitted in any actions or proceedings allowed by law.

IN WITNESS WHEREOF, the Companies have caused this instrument to be signed, and their corporate seals to be hereto affixed, this 4th day of March, 2024.



State of Connecticut

City of Hartford ss.

By: 
 Bryce Grissom, Senior Vice President

On this the 4th day of March, 2024, before me personally appeared Bryce Grissom, who acknowledged himself to be the Senior Vice President of each of the Companies, and that he, as such, being authorized so to do, executed the foregoing instrument for the purposes therein contained by signing on behalf of said Companies by himself as a duly authorized officer.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

My Commission expires the 30th day of June, 2026




 Anna P. Nowik, Notary Public

This Power of Attorney is granted under and by the authority of the following resolutions adopted by the Boards of Directors of each of the Companies, which resolutions are now in full force and effect, reading as follows:

RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President, any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary may appoint Attorneys-in-Fact and Agents to act for and on behalf of the Company and may give such appointee such authority as his or her certificate of authority may prescribe to sign with the Company's name and seal with the Company's seal bonds, recognizances, contracts of indemnity, and other writings obligatory in the nature of a bond, recognizance, or conditional undertaking, and any of said officers or the Board of Directors at any time may remove any such appointee and revoke the power given him or her; and it is


FURTHER RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President may delegate all or any part of the foregoing authority to one or more officers or employees of this Company, provided that each such delegation is in writing and a copy thereof is filed in the office of the Secretary; and it is

FURTHER RESOLVED, that any bond, recognizance, contract of indemnity, or writing obligatory in the nature of a bond, recognizance, or conditional undertaking shall be valid and binding upon the Company when (a) signed by the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary and duly attested and sealed with the Company's seal by a Secretary or Assistant Secretary; or (b) duly executed (under seal, if required) by one or more Attorneys-in-Fact and Agents pursuant to the power prescribed in his or her certificate or their certificates of authority or by one or more Company officers pursuant to a written delegation of authority; and it is

FURTHER RESOLVED, that the signature of each of the following officers: President, any Executive Vice President, any Senior Vice President, any Vice President, any Assistant Vice President, any Secretary, any Assistant Secretary, and the seal of the Company may be affixed by facsimile to any Power of Attorney or to any certificate relating thereto appointing Resident Vice Presidents, Resident Assistant Secretaries or Attorneys-in-Fact for purposes only of executing and attesting bonds and undertakings and other writings obligatory in the nature thereof, and any such Power of Attorney or certificate bearing such facsimile signature or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by such facsimile signature and facsimile seal shall be valid and binding on the Company in the future with respect to any bond or understanding to which it is attached.

I, Kevin E. Hughes, the undersigned, Assistant Secretary of each of the Companies, do hereby certify that the above and foregoing is a true and correct copy of the Power of Attorney executed by said Companies, which remains in full force and effect.

Dated this February 7, 2025




 Kevin E. Hughes, Assistant Secretary

To verify the authenticity of this Power of Attorney, please call us at 1-800-421-3880.
 Please refer to the above-named Attorney(s)-in-Fact and the details of the bond to which this Power of Attorney is attached.

**THE
UNIVERSITY
OF RHODE ISLAND**

**DIVISION OF
ADMINISTRATION
AND FINANCE**

THINK BIG  WE DO™

PURCHASING DEPARTMENT
210 Flagg Road, Kingston, RI 02881 USA p: 401.874.2171 f: 401.874.2306 uri.edu/strategic-procurement/purchasing



DATE: February 5th, 2025

Addendum# 2

BID NO.: 101448
OPENING: 2/7/25 at 2:00 PM
COMMODITY: CONSTRUCTION OF NEW 400' RADIO TOWER & TRANSMITTER BLDG.

Due to inclement weather the bid opening is being extended from 2/6/25 at 1:00 PM to 2/7/25 at 2:00 PM.

Andrea Boucher Digitally signed by Andrea
Boucher
Date: 2025.02.05 08:40:43 -05'00'

Purchasing Department
The University of Rhode Island

Rev. 6-7-24

**THE
UNIVERSITY
OF RHODE ISLAND**

**DIVISION OF
ADMINISTRATION
AND FINANCE**

THINK BIG  WE DO™

PURCHASING DEPARTMENT
210 Flagg Road, Kingston, RI 02881 USA p: 401.874.2171 f: 401.874.2306 uri.edu/strategic-procurement/purchasing




DATE: January 21st, 2025

Addendum# 1

BID NO.: 101448
OPENING: 2/6/25 at 1:00 PM
COMMODITY: CONSTRUCTION OF NEW 400' RADIO TOWER & TRANSMITTER BLDG.

This addendum is being issued to make the following clarifications:

1. The bid opening is being extended from 1/30/25 at 2:00 PM to 2/6/25 at 1:00 PM.
2. Provide answers to the questions received by the deadline posted in the above referenced bid.
3. Provide a copy of the Non-Mandatory Pre-Bid Sign-In Sheet.

Andrea Boucher  Digitally signed by Andrea
Boucher
Date: 2025.01.21 13:56:50 -05'00'

Purchasing Department
The University of Rhode Island

Rev. 6-7-24

**THE
UNIVERSITY
OF RHODE ISLAND**

**DIVISION OF
ADMINISTRATION
AND FINANCE**

THINK BIG  WE DO™

PURCHASING DEPARTMENT
210 Flagg Road, Kingston, RI 02881 USA p: 401.874.2171 f: 401.874.2306 uri.edu/strategic-procurement/purchasing



**BID 101448 – CONSTRUCTION OF NEW 400’ RADIO TOWER & TRANSMITTER BLDG.
QUESTIONS AND ANSWERS**

1. I do not see the Geo report called out in the spec document... Snip below:

The replacement tower and guy wire foundations shall be designed in accordance with the Geotechnical Investigation Report prepared by Tectonic Engineering Consultants, P.C. dated 8/30/23. B. Entire report and additional information are attached in Appendix E.

Please let me know how to find it as it is not on the Purchasing portal.

Answer 1: Geotechnical report has been completed and is attached to this addendum.

2. Geo Tech Report required to complete Bidding. Do you guys have Geo Tech Report?

Answer 2: Please see Answer 1.

3. Do you require PE Stamped CD for Tower & Foundation of Tower Only?

Answer 3: Yes, as this is a delegated design. The Tower and foundation drawings and calculations shall be signed and sealed in the State of Rhode Island.

4. Design Criteria DATA Required:

- a. 3 sec wind Guest with Ice
- b. 3 sec wind Guest No Ice
- c. As per CD Ice Thickness 1 inch, Reduction Applied, or No?
- d. Is the Building Code TIA 222-H-2017 or TIA-G-2005?

Answer 4: See sheet T003 for design criteria. The design shall be in accordance with TIA 222-H.

5. How many Gangs Meter Bank Required:

- a. C101 said 2 Gang
- b. C200 ask for 4 Gang
- c. E100 said 2 Gang
- d. E101 ask for Multi Gang

Answer 5: We are designing the compound for 1 future carrier. A minimum of 2 is required.

6. Detail of Antenna Quantity / Model and Mount detail as well.

Answer 6: See chart on C200 for details. Antenna: Shively 6813-4.

**THE
UNIVERSITY
OF RHODE ISLAND**

**DIVISION OF
ADMINISTRATION
AND FINANCE**

THINK BIG  WE DO™

PURCHASING DEPARTMENT
210 Flagg Road, Kingston, RI 02881 USA p: 401.874.2171 f: 401.874.2306 uri.edu/strategic-procurement/purchasing



A ring-stub, pressurized, FM antenna with a slug matching transformer.
A power gain of 2.14 or 3.3 db when full-spaced.
Right-circular polarization and a 1 5/8 inch input connection.
High density polyethylene four element radomes to protect against ice and snow collection on elements.
the Shively antennas come with their own mounts because the spacing between the bays and the tower leg is crucial to the antenna's performance.

7. Lighting Detail Required (Our Concern is giving below):

Lighting Requirements

1. System Type:

- a. **Red Obstruction Lighting System** (L-810 for steady-burning lights, L-864 for flashing lights) OR
- b. **Dual Lighting System** (medium-intensity white lights for daytime and twilight, and red lights for nighttime).

Answer 7.1: DUAL MODE tower lighting is desired and encouraged by the FAA and FCC, (white lights day and red at night)

2. Levels of Lights:

- a. For a tower of 400 ft, 3 levels of lights are typically required:
 - a. **Top Level:**
 1. At least one red flashing light (L-864) for nighttime visibility.
 2. Alternatively, medium-intensity flashing white light (L-865) for 24-hour operation.
 - b. **Intermediate Levels:**
 1. Two or more lights per level positioned at diagonally opposite locations for redundancy and visibility.
 2. Typically required at approximately 150 ft and 300 ft (spaced evenly).
- b. **Ground Level/Lower Structures:**
 - a. Additional steady-burning red lights (L-810) may be installed if the lower sections are obstructed by terrain, vegetation, or buildings.

Answer 7.2: Elevations of lights confirmed as noted above. May change based on final design but use for bidding purposes.

3. Horizontal Placement:

- a. Lights must be installed to ensure 360-degree visibility for aircraft, with no obstructions to the light from any direction.

Answer 7.3: This is correct.

**THE
UNIVERSITY
OF RHODE ISLAND**

**DIVISION OF
ADMINISTRATION
AND FINANCE**

THINK BIG  WE DO™

PURCHASING DEPARTMENT
210 Flagg Road, Kingston, RI 02881 USA p: 401.874.2171 f: 401.874.2306 uri.edu/strategic-procurement/purchasing



Number of Locations to Install:

- **Top Level:** 1 location with a red flashing light (or white medium-intensity light).
- **Intermediate Levels:** 2 levels, each with at least 2 lights (diagonally opposite placement).
- **Total Locations:** At least 3 levels, with lights positioned to provide full horizontal coverage.

Answer: Confirmed for pricing. May change once final tower design has been completed

Additional Notes:

- **Ice Shields:** Required in icing-prone areas to protect light fixtures.

Answer: Ice protection required as shown on drawings.

- **Automatic Monitoring:** Systems should be monitored automatically or visually inspected regularly for functionality.

Answer: Automatic monitoring of the tower lights and other parameters like, inside temperature, transmitter output, and unauthorized entry will be handled by the station's extensive required remote control monitoring which is required by the FCC.

8. Any Accessories needs to Add:

- **Anti-Climb**
- **Safety Climb**
- **TIA Grounding**
- **Step Bolts**
- **Waveguide Ladder**
- **Antenna Mounts**

Answer 8: Yes, to all of the above

9. Does URI possibly have the original tower foundation and guy anchor foundation details?

Answer 9: Yes, original tower by Rohn. Drawings are attached to this addendum.

10. Is there any drawings or foundation details for the existing block building to be removed?

Answer 10: Yes, all existing foundations shall be removed and new foundations to be installed. We do not have original drawings for this building or the foundation.

11. There are large trees along the cleared new guy paths that were discussed with the need to remove etc. Is there an actual drawing showing how many of these large trees are required to be removed? Or does URI have an idea of how many to be removed?

**THE
UNIVERSITY
OF RHODE ISLAND**

**DIVISION OF
ADMINISTRATION
AND FINANCE**

THINK BIG  WE DO™

PURCHASING DEPARTMENT
210 Flagg Road, Kingston, RI 02881 USA p: 401.874.2171 f: 401.874.2306 uri.edu/strategic-procurement/purchasing



Answer 11: A survey will need to be completed to confirm which trees will be required to be removed. Any tree within the fall zone shall be removed. An allowance has been included for this line item.

12. Can URI please provide geotechnical report in order to nail down proposed tower design and foundations?

Answer 12: Please see Answer 1.

13. What does the University consider “a substantial portion of the work” that needs to be self-performed?

Answer 13: The awarded vendor is meant to be held to the stated requirements and while subcontracting may be allowed for certain portions of the work (i.e. tree removal), the detailed requirements are not meant to be subcontracted.

14. What would be a “disproportionate amount” of the work for a subcontractor to be assigned?

Answer 14: The awarded vendor is meant to be held to the stated requirements and while subcontracting may be allowed for certain portions of the work (i.e. tree removal), the detailed requirements are not meant to be subcontracted.

15. Is the sign-in sheet from the pre-bid proposal conference available?

Answer 15: Yes, a copy of the Non-Mandatory Pre-Bid Sign-In Sheet is attached to this addendum.

16. What is the schedule for construction? Substantial completion?

Answer 16: Please refer to the bid solicitation. This information is available on the bid form.

17. Officially, what is the website/url for where project information / addendums / etc. are posted?

Answer 17: Bid solicitations including addendums are posted here:
<https://purchasing.ri.gov/bidding/externalbidsearch.aspx>

Please search by the applicable bid number.

18. Are there any liquidated damages? If so, what’s the value?

Answer 18: Please refer to the bid solicitation. This information is available on the bid form.

19. Please provide sign-in sheet/attendee list from the walkthrough.

**THE
UNIVERSITY
OF RHODE ISLAND**

**DIVISION OF
ADMINISTRATION
AND FINANCE**

THINK BIG  WE DO™

PURCHASING DEPARTMENT
210 Flagg Road, Kingston, RI 02881 USA p: 401.874.2171 f: 401.874.2306 uri.edu/strategic-procurement/purchasing



Answer 19: Please see Answer 15.

20. Page 7 on the project plans appears to be incomplete, see attached. Is the full page available?

Answer 20: Yes, attached to this addendum are the correct drawings.

21. Is there a geotechnical report available for this project?

Answer 21: Please see Answer 1.

22. Are there any W/MBE requirements for this project? Apprenticeship requirements?

Answer 22: Yes, please refer to the bid solicitation.

23. Will there be any FAA requirements/standards?

Answer 23: Yes, see lighting answer in section 7. We need to keep the NOTAM in effect as long as there we anticipate that will be a replacement tower of the same height at that site. The old tower shows up on pilot sectionals (mape) which every pilot should have and the NOTAM refers back to those sectionals.

24. We are To Purchase Everything Here Correct?

**Tower
Generator
All Labor and Materials**

Answer 24: Correct.

25. Is this a Prevailing Wage?

Answer 25: Yes, please refer to the bid solicitation regarding prevailing wage requirements.

26. Can you please supply the exact models of antennas that will be required so proper loading can be factored into the design calculations?

Answer 26:

Antenna: Shively 6813-4

A ring-stub, pressurized, FM antenna with a slug matching transformer.

A power gain of 2.14 or 3.3 db when full-spaced.

Right-circular polarization and a 1 5/8 inch input connection.

High density polyethylene four element radomes to protect against ice and snow collection on elements.

**THE
UNIVERSITY
OF RHODE ISLAND**

**DIVISION OF
ADMINISTRATION
AND FINANCE**

THINK BIG  WE DO™

PURCHASING DEPARTMENT

210 Flagg Road, Kingston, RI 02881 USA

p: 401.874.2171

f: 401.874.2306

uri.edu/strategic-procurement/purchasing



the Shively antennas come with their own mounts because the spacing between the bays and the tower leg is crucial to the antenna's performance.

University of Rhode Island
Office of Capital Projects
60 Tootell Road, Sherman Bldg.
Kingston, Rhode Island 02881

Attention: Kyle Coleman, P.E., Construction Manager
(Via email: kycoleman@uri.edu)

August 30, 2023

RE: W.O. 12117.01
GEOTECHNICAL INVESTIGATION
PROPOSED 400-FOOT GUYED TOWER
URI RADIO GUYED TOWER
875 PLAINS ROAD
SOUTH KINGSTOWN, WASHINGTON COUNTY, RHODE ISLAND

Dear Mr. Coleman:

Tectonic Engineering Consultants, Inc. (Tectonic) has performed a subsurface investigation and geotechnical engineering analyses for the proposed guyed tower at the above referenced site. This report presents our findings and recommendations for the design and construction of the foundations for the proposed tower.

1.0 DESIGN CONSIDERATIONS

The proposed tower is a guyed tower structure that will be used to mount communication antennas. It is expected that the guyed tower foundation will be subjected to relatively high overturning loads resulting in tension loads on the guy anchors, whereas static compressive loads at the base of the tower will be modest, in comparison. The actual loads from the guyed tower are to be determined by others.

In accordance with the publication entitled “Structural Standard for Antenna Supporting Structures and Antennas and Small Wind Turbine Support Structures” (TIA-222-H), it shall be permissible to determine seismic design parameters from the ASCE 7 online Hazard Tool based on ASCE 7-16. Additionally, it is our understanding that the monopole tower is categorized as Risk Category II.

2.0 SCOPE OF SERVICES

The following services were performed for The University of Rhode Island - Office of Capital Projects, hereafter referred to as Client.

- Review of geological information publicly available through the United States Geological Survey (USGS) and the National Resources Conservation Service (NRCS).
- Drilling, sampling, and logging of four (4) borings, designated as borings B-1 through B-4, to approximate depths up to 22 feet below existing grade (bgs).

Newburgh Office

1279 Route 300 | Newburgh, NY 12550
845.567.6656 Tel | 845.567.6248 Fax

tectonicengineering.com
Equal Opportunity Employer

- Field inspection by a Tectonic representative, working under the purview of a Rhode Island State licensed Professional Engineer, to locate the borings; and log and classify all soil samples.
- Performance of in-situ soil resistivity testing by a Tectonic representative at two (2) locations in the general center of the project site.
- Laboratory testing of soil samples selected to verify the field classifications and corrosivity potential of the underlying soil, and to evaluate the engineering characteristics of the soil.
- Geotechnical engineering analyses of the subsurface conditions and laboratory test results as they relate to the design and construction of the foundations of the proposed guyed tower.
- Preparation of this geotechnical report presenting the results of the subsurface investigation, laboratory testing, engineering analyses, and our geotechnical recommendations as they relate to the design and construction of the foundations of the proposed guyed tower.

3.0 SITE AND PROJECT DESCRIPTIONS

The project site (site) is in an undeveloped land parcel, at the general end of Plains Road, South Kingstown, Washington County, Rhode Island. A previously constructed guyed tower, that has since been demolished, is purported to have existed in the general area, with concrete remnants visually observed during the Tectonic subsurface investigation. The site is bordered by heavily wooded areas on all sides, with an existing one-story structure in the general northwest portion of the site. Based on our onsite observations and review of a provided existing conditions topographic survey, prepared by Narragansett Engineering Inc. (NEI), Project # 21.0133, dated August 9, 2023, the site slopes downward to the north-northwest. Ground surface elevations range from approximately +175 to +144 feet. All elevations listed reference the North American Vertical Datum of 1988 (NAVD 88)

Per our discussion with members of the design team, the proposed project consists of the construction of an approximately 400-foot guyed tower, to be constructed in the same general footprint area of the previously referred and demolished guyed tower. Additionally, three (3) deadmen anchors will be constructed for support of the proposed tower. Structural loading was not available as of the preparation of this report. Also, no significant grading, or cutting and filling, is anticipated for construction of the proposed tower and deadmen anchors.

4.0 SUBSURFACE INVESTIGATION

The subsurface investigation consisted of the drilling, sampling, and logging of four (4) test borings, designated as borings B-1 through B-4. Boring B-1 was drilled approximately nine-feet offset of the previously demolished guyed tower base, and borings B-2 through B-4 were advanced approximately 11 to 16 feet offset of the **previously demolished guyed tower concrete anchorage. As previously mentioned, it is Tectonic's understanding** that the proposed guyed tower and concrete anchorages will be constructed in the same general footprint areas as the previously demolished structures. The approximate locations of the borings are indicated on the attached Location Plan, Figure 1.

The borings were performed by Geologic Earth Exploration, Inc. on July 19 and 20, 2023 using an Acker Recon ATV-mounted drill rig, equipped with an automatic hammer. The borings were advanced through overburden soil using 2-7/8-inch tricone roller bits and mud-rotary drilling techniques. Soils were stabilized with 4-inch nominal diameter driven steel casing. Standard Penetration Testing (SPT) and split-spoon sampling was performed within the borings and was performed in general accordance with the requirements of ASTM Standard D1586 Standard Test Method for Penetration Test and Split-Barrel Sampling of Soils. SPT N-values were recorded for each soil sample taken. Samples of the soil obtained during the investigation were collected, retained, and are currently stored at our material testing laboratory. Upon completion, the boreholes were backfilled with drill cuttings to match the existing conditions.

All drilling, sampling, and logging of the borings, and soil resistivity testing, were performed under the full-time observation of a Tectonic representative working under the supervision of a Professional Engineer licensed in the State of Rhode Island. The Tectonic representative classified and collected soil samples for laboratory testing at the boring locations as they were recovered, and prepared logs of the soil and groundwater conditions encountered. The soils were classified in accordance with the latest edition of the Rhode Island State Building Code (Code), the Burmister Soil Classification System, and the Unified Soil Classification System (USCS) (ASTM D2488). Copies of the boring and soil resistivity test logs are attached.

5.0 RESISTIVITY TESTING

Soil resistivity testing was performed at the site and was completed on July 19, 2023. The testing was performed in general conformance with ASTM Standard G57 and consisted of the performance of two (2) Wenner arrays, designated as Test 1 and Test 2. The tests were performed approximately perpendicular to each other, in the approximate center position of the site. A more detailed location of the testing can be found on Figure 1.

The resistivity testing was performed with an AEMC Industries Model 6472 digital Ground Resistance Tester, using Wenner electrode "a" spacings of 2.5, 5, 10, 20 and 35 feet. Note, specific electrode spacing was not provided by the client, and therefore a generalized standard spacing was used. The data presented below in Table 5.1 includes the calculated earth resistivity, based on the measured resistance at each "a" spacing, which per the assumption of the Wenner array method, represents the average earth resistivity of a hemisphere of soil having a radius equal to the "a" spacing. Resistivity test logs are included in Appendix III.

| Table 5.1 - Resistivity Test Results | | | | | |
|--|-------------------|---------|---------|---------|---------|
| Measured Resistivity for Varying "a" Spacings (Ohm Cm) | | | | | |
| Array Number | Electrode Spacing | | | | |
| | 2.5 Ft | 5 Ft | 10 Ft | 20 Ft | 35 Ft |
| Test 1 | 219,759 | 305,461 | 315,994 | 250,114 | 252,029 |
| Test 2 | 208,747 | 296,843 | 354,296 | 275,393 | 268,786 |

6.0 LABORATORY TESTING

Laboratory testing consisted of six (6) Standard Test Methods for Particle-Size Distribution (Gradation) of Soils Using Sieve Analysis performed in general accordance with ASTM D6913; and soil chemical (corrosivity) testing. Soil corrosivity testing was performed on two (2) composite soil samples collected from the borings. The

corrosivity testing includes a suite of tests to measure the chloride and sulfate contents, and pH of the soil. The laboratory test results are attached and incorporated into the soil descriptions presented in the following section.

7.0 SUBSURFACE CONDITIONS

The results of the subsurface investigation, and information obtained from the NRCS, indicate that the site is primarily underlain by glacially deposited soils, primarily consisting of coarse sands and silty melt-out till derived from granite and gneiss. The following subsections provide general descriptions of the subsurface conditions encountered. More detailed descriptions are provided on the boring logs, and the laboratory test results, attached.

As previously mentioned, an automatic hammer was used in the performance of the SPT sampling. The energy standardized N_{60} -value, which is typical of a safety hammer and is the standard for geotechnical analyses, is also used in the following descriptions of the soils. An automatic hammer typically imparts about 1.3 times as much energy to the soil as a safety hammer, and therefore, the field N-values reported in the boring logs are corrected by this factor to obtain the energy-corrected SPT N_{60} -values.

7.1 Native Soils

Native soils were encountered from the ground surface to the total depth explored in all borings. The native soils generally consisted of variably colored, coarse-to-fine sand, with varying amounts of coarse-to-fine gravel and silt. Pockets of coarse to fine gravel, as the primary material constituent, were encountered in all borings except boring B-3, and a small pocket of silt was encountered in the upper 2 feet bgs in boring B-1. Field SPT N-values within the native soils ranged from 4 blows per foot (bpf) to split spoon sampler refusal, which is defined as less than 6 inches of sampler penetration for 50 blows of the hammer. When corrected, the SPT N_{60} -values ranged from approximately 5 bpf to sampler refusal, indicating a loose to very dense condition. On average the native soils were encountered in a dense to very dense condition, with the loose layer only occurring in the upper 2 feet bgs in boring B-3. Additionally, note should be taken that numerous obstructions, in the form of cobbles and boulders, were encountered at varying and multiple depth layers in all borings. Auger refusal, on apparent cobble/boulder obstructions, was also encountered at the termination depth of all borings. The native soils have a USCS designation of SM and GM.

7.2 Groundwater

Due to the introduction of drilling fluid during mud rotary drilling, accurate groundwater readings could not be obtained during advancement of the borings. Groundwater, in the form of saturated soil samples, was observed in all borings at approximate depths ranging from 6 to 8 feet bgs. However, it should be noted that long-term measurements of groundwater were not part of the provided scope of services, and if required, Tectonic recommends the installation of a groundwater observation well. Additionally, groundwater levels vary seasonally, and with changing weather conditions. Consequently, groundwater may be encountered at other depths at other times, and in a perched condition above the very dense and fine-grained soils.

7.3 Soil Corrosivity

As noted in Section 5, chemical testing was performed on composite soil samples to evaluate the chloride and sulfate contents, pH, and electrical resistivity of the soils on site. Within the borings, composite samples were collected from the uncontrolled fill and native soils. The chemical testing was performed by Phoenix Environmental Laboratories, Inc. at their testing laboratory located in Manchester, Connecticut. Table 7.3.1 summarizes the results of the laboratory testing and the resulting relative corrosivity and resistivity of the subsurface soil at the site. The laboratory test report is included in Appendix II of this report.

| Soil Type | Sample No. | Depth (ft) | Chloride Content (mg/kg ³) | pH | Sulfate Content (mg/kg ³) | Relative Corrosivity |
|------------|------------|------------|--|------|---------------------------------------|----------------------|
| Tower Base | Composite | 2 to 10 | < 55 | 6.60 | < 55 | Negative |
| Deadmen | Composite | 2 to 8 | < 54 | 6.26 | < 54 | Negative |

Notes:

1. Reference: "Understanding Soil Risks and Hazards Using Soil Survey to Identify Areas with Risks and Hazards to Human Life and Property" USDA
2. The ratio mg/kg is equal to parts per million (ppm).
3. Content values preceded with a less than symbol (<) indicate that the content was below the detectable limit.

8.0 SITE CLASS AND SEISMIC SITE COEFFICIENTS

Based on the results of the subsurface investigation and the criteria outlined in the current edition of the Code and TIA-222-H, the subsurface conditions underlying the site should be considered Class D. The associated seismic design parameters from ASCE 7 are attached.

9.0 GUYED TOWER FOUNDATION RECOMMENDATIONS

Based on our understanding of the project and our conversations with the design team, the proposed construction will consist of the construction of an approximately 400-foot tall guyed tower. The following sub-sections provide our geotechnical recommendations for design and construction of the proposed guyed tower foundations. The recommendations are based on our understanding of the proposed construction, the results of the subsurface investigation, and our experience on other similar projects.

9.1 Tower Base and Guy Anchorages

The proposed guyed tower base can be supported on a conventional shallow spread footing (concrete block) that bears on the very dense native soils encountered at the site around boring B-1. The foundation can be designed for a maximum net allowable soil bearing pressure of 6,000 pounds per square foot (psf). Section 10 of this report provides the subgrade preparation procedures necessary to achieve the recommended bearing capacity. Using the above design criteria, total settlement is estimated to be up to 1 inch. It is recommended that the concrete block has a minimum width of 3.0 feet, and should bear at least 4.5 feet below outside grade, for frost protection.

Each of the guy anchorages will resist the uplift and lateral forces exerted by the guy wires through a combination of dead weight, resistance to soil shear along the anticipated failure planes, and passive earth pressure. The passive earth pressure will occur, because of the lateral loading, along the face of the concrete blocks that are oriented perpendicular to the direction of the guy anchor and are closest to the tower. Frictional resistance will also be developed along the sides and base of the block in the opposite direction of the applied force.

As previously mentioned, groundwater was encountered as shallow as approximately 6 feet bgs. A seasonally high depth to groundwater of 4 feet bgs should be used for design. Based on this depth, and the anticipated bearing depth of the proposed tower base and guy anchorages, construction phase dewatering may be required. Contractors, and others involved, should be prepared for the need to dewater.

The table below provides recommended soil parameters for use in evaluating the soil resistance to the imposed lateral and uplift loads:

| Soil Parameter | Native Soils - Approximate Depth Below Existing Grade (ft.) | | Imported Structural Fill |
|--|---|-----------------|--------------------------|
| | 0 to 4 | Below 4 | |
| Angle of Internal Friction | 32° | 36° | 34° |
| Active Earth Pressure Coefficient (Ka) | 0.31 | 0.26 | 0.28 |
| Passive Earth Pressure Coefficient (Kp) ² | 3.25 | 3.85 | 3.54 |
| At-Rest Earth Pressure Coefficient (Ko) | 0.47 | 0.41 | 0.44 |
| Coefficient of Base Friction ³ | 0.35 | 0.45 | 0.42 |
| Unit Weight of Soil (pounds per cubic foot) | 115 | 67 ¹ | 125 |

- 1) Assumes a seasonally high depth to groundwater of 4 feet bgs.
- 2) Reduce the passive pressure above a depth of 4.5 feet below exterior grade by half to account for frost disturbance.
- 3) Coefficient of base friction applies to mass concrete placed directly against material indicated.

9.2 Foundation Construction Considerations

The foundation subgrades should be prepared by excavating to the bearing depth using hydraulic excavation equipment and using hand equipment to remove all soil and broken cobble and boulder materials loosened by excavation. The subgrade should then be inspected by the geotechnical engineer to verify that the materials are consistent with those described in this report. Any unsuitable materials (broken cobbles or boulders or soil other than those recommended for bearing) should be removed as directed by the geotechnical engineer.

Numerous cobbles and boulders were encountered during the subsurface investigation. Contractors involved in the excavation for the foundation of the proposed guyed tower should be prepared for the need for their removal.

Although not anticipated, any new fill slopes should be constructed on a slope inclination no steeper than 3 to 1 (Horizontal to Vertical) unless a detailed slope stability evaluation is performed. The sides of the excavation should be sloped back for safety unless a sheeting or bracing system is used. The Occupational Safety and Health Administration (OSHA) and other applicable agency requirements pertaining to worker safety should be met during the excavation activities.

10.0 EARTHWORK CONSTRUCTION CRITERIA

The following sections present our recommendations regarding earthwork and construction monitoring.

10.1 General Site Preparation and Excavations

Initially, the site should be stripped of all topsoil-like material and organics, debris, and vegetation. Debris and vegetation from the clearing operations should be removed from the site and disposed of at a legal dump site. All soft or unsuitable native materials, and subsurface obstructions, should be removed from the mat foundation footprint.

If encountered, any existing utilities within the project limits should be excavated and re-routed or removed. The resulting excavations should be backfilled with structural fill in accordance with the procedures outlined in Section 10.3. Trench excavations should be properly benched to allow for adequate compaction.

All excavations should conform to the latest OSHA requirements regarding worker safety. Based upon the soils encountered within the borings, the soils at the site should be considered OSHA Type C soils.

10.2 Foundation and Subgrade Preparation

All subgrades should be inspected by the Tectonic geotechnical engineer prior to the placement of structural fill, steel, or concrete. The foundation subgrade should be prepared by excavating to the bearing depth using hydraulic excavation equipment.

All foundation subgrades should also be proofrolled and be recompacted after excavation using the largest compaction equipment that can be practicably operated in the foundation excavation, such as a heavy plate tamper, or a trench roller, under the full-time observation of the geotechnical engineer. Any unsuitably yielding material should be removed and replaced as described above.

After the soil subgrade has been inspected and approved by the geotechnical engineer, an approximate 4-inch layer of free draining (Item #57 or similar) crushed stone can be placed to protect the subgrade and act as a working platform during construction.

10.3 Fill and Backfill Materials

The existing fill and native soils, due to their high fines content, are not suitable for structural fill, but may be used as general fill, such as in landscape areas. Imported structural fill materials should consist of clean imported on-site sand, gravel, crushed stone, crushed gravel, or a mixture of these, and should contain no organic matter and should meet the gradation as specified in the Rhode Island State Department of Transportation (RIDOT) Standard Specifications for Road and Bridge Construction, Section M.01.09, Gradation of Aggregates, Reclaimed Processed Material, and as recommended below.

| <u>Sieve Size</u> | <u>Percent Finer by Weight</u> |
|-------------------|--------------------------------|
| 3-inch | 100 |
| 1-1/2-inch | 70 - 100 |
| 3/4-inch | 50 - 85 |
| No. 4 | 30 - 55 |
| No. 50 | 8 - 25 |
| No. 200 | 2 - 10 |

All structural fill should be compacted to at least 95 percent of the maximum dry density at near optimum moisture contents as determined by ASTM Standard D1557, "**Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN-m/m³))**". The lift thickness for the fill soils will vary depending on the type of compaction equipment used. Fills should generally be placed in uniform horizontal lifts not exceeding 8 inches in loose thickness. In confined areas, the loose lift thickness should be reduced to 4 inches or less and each lift should be compacted with sufficient passes of hand operated vibratory or impact compaction equipment.

A geotechnical engineer with appropriate field and laboratory support should approve materials for use as fill, and test fill materials for compliance with the recommended compaction. Each lift of fill placed at the site should be tested for compaction.

10.4 Construction Dewatering and Protection of Subgrades

Approved subgrades should be protected from the effects of frost, construction traffic, perched groundwater, surface water, and precipitation. The necessary protection should be provided as soon after acceptance, as is practicable, and should be maintained until coverage with compacted fill or concrete. It is recommended that temporary surface drainage measures be installed to divert runoff away from the proposed construction limits.

Depending on the foundation bearing depths of the tower base and guy anchorages, construction phase dewatering may be warranted, and if required it should be performed in a manner that will prevent loosening or migration of the subgrade soils.

The operation of sumps directly in the foundation excavation should not be allowed. Sump pits should be placed at least 1 foot outside of foundation excavations for every foot below the foundation subgrade elevation that they excavated. As per our field observations, the on-site soils were observed to contain significant amounts of silt, which make them moisture sensitive. They will readily soften and experience a reduction in load-carrying capacity when exposed to moisture. These soils are also frost susceptible and will experience expansion and contraction during freeze-thaw cycles.

11.0 LIMITATIONS

Our professional services have been performed using that degree of care and skill ordinarily exercised under similar circumstances by reputable geotechnical engineers and geologists practicing in this or similar situations. The interpretation of the field data is based on good judgment and experience. However, no matter how qualified the geotechnical engineer or detailed the investigation, subsurface conditions cannot always be predicted beyond the points of actual sampling and testing. No other warranty, expressed or implied, is made as to the professional advice included in this report.

The recommendations contained in this report are for design purposes only. Contractors and others involved in this project are advised to make an independent assessment of the subsurface conditions for the purpose of estimating quantities and scheduling. No warranty, express or implied, is made as to the advice provided in this report.

This report has been prepared for the exclusive use of the Client for the specific application to the proposed construction detailed in this report. If any changes in the design or location of the proposed construction is planned, the conclusions and recommendations contained in this report shall not be considered valid unless reviewed and verified in writing by Tectonic Engineering Consultants, Inc. It is recommended that Tectonic be retained to provide construction monitoring services to ensure proper implementation of the recommendations contained herein, which would otherwise limit our professional liability.

We trust this report will allow you to proceed with design of the existing foundations.

Sincerely,


TECTONIC ENGINEERING CONSULTANTS, INC.
DONALD A. BENVIE

Prepared by:


No.  6345
Donald A. Benvie, P.E.
President & CEO REGISTERED
PROFESSIONAL ENGINEER

CDF/CBB/DB 6 Newburgh Geotechnical\12100\12117.01 URI Radio Tower System\Report\12117.01.Geo Report.docx

Attachments: Boring Location Plan, Figure 1
 Boring Logs, By Tectonic
 Soil Resistivity Results, by Tectonic
 Laboratory Results, by Tectonic and Phoenix




LEGEND

- B-4 APPROXIMATE BORING LOCATION
- R-2 APPROXIMATE SOIL RESISTIVITY TEST LOCATION

NOTES

1. PLAN BASED ON A TOPOGRAPHIC SURVEY PROVIDED BY THE CLIENT, TITLED "EXISTING CONDITIONS SURVEY AND TOPOGRAPHY PLAN", DRAWING NO. SV-101, DATED 08/09/23.
2. BORING AND SOIL RESISTIVITY TEST LOCATIONS WERE FIELD LOCATED BY SECTION C AND SHOULD BE CONSIDERED APPROXIMATE.



Tectonic
 PRACTICAL SOLUTIONS. EXCEPTIONAL SERVICE.

Tectonic Engineering Consultants, Inc.
 70 Pleasant Hill Road
 P.O. Box 37
 Mount Airy, NY 10953
 Project Control Info
 1279 Route 300
 Newburgh, NY 12550

Phone: (845) 834-5959
 (800) 829-6531
 www.tectonic-engineering.com
 Phone: (845) 567-8556

| BORING AND SOIL RESISTIVITY TEST LOCATION PLAN | | | |
|---|------------------------|-------------------------|----------|
| URI RADIO TOWER SYSTEM PLAINS ROAD SOUTH KINGSTOWN, WASHINGTON COUNTY, RHODE ISLAND | | | |
| Date 08/30/23 | Work Order 12117.01 | Drawing No. FIGURE 1 | Rev 0 |
| Scale 1" = 40' | | | |



PROJECT No. 12117.01
 PROJECT: URI Radio Tower System
 LOCATION: 875 Plains Rd, South Kingstown, RI

BORING No. B-1
 SHEET No. 1 of 1

| | | | | | |
|---|--------------|----------|---------------------------------|---|----------------------------|
| CLIENT: URI | GROUND WATER | DATE | TIME | DEPTH | INSPECTOR: Connor McCleary |
| CONTRACTOR: Geo Logic - Earth Exploration, Inc. | | | | | DRILLER: Damien Jacobs |
| METHOD OF ADVANCING BORING | DIA. | DEPTH | | | SURFACE ELEVATION: 165.5 |
| POWER AUGER: | | TO | MON. WELL | <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO | DATUM: See Remarks |
| ROT. DRILL: | 2 7/8" | 0 TO 22' | SCREEN DEPTH: | — TO — | DATE START: 7/20/23 |
| CASING: | 4" | 0 TO 22' | WEATHER: Clear | TEMP: 75° F | DATE FINISH: 7/20/23 |
| DIAMOND CORE: | | TO | DEPTH TO ROCK: Not Encountered* | UNCONFINED COMPRESS. STRENGTH (TONS/FT) | |
| Acker Rebel Track Rig with Automatic Hammer | | | *CHANGES IN STRATA ARE INFERRED | | |

| DEPTH (FT.) | N OR MIN./FT. | PENETRATION RESISTANCE (BL/6 IN.) | SAMPLES | | | MOISTURE | UNIFIED SOIL CLASS. | DESCRIPTION OF MATERIAL | LITHOLOGY* | UNCONFINED COMPRESS. STRENGTH (TONS/FT) | | | ELEVATION (FT.) | |
|-------------|---------------|-----------------------------------|---------------|---------------------|---------|----------|---------------------|---|------------|---|---|---|-----------------|-------|
| | | | SAMPLE NUMBER | RECOV. LENGTH (IN.) | RQD (%) | | | | | 1 | 2 | 3 | | 4 |
| 1 | 14 | 2 | S-1 | 20 | | M | SM | Bwn-gy Silt, and c-f Sand, little f Gravel | | | | | | |
| 2 | | 12 | | | | | | | | | | | | |
| 3 | 62 | 38 | S-2 | 17 | | M | SM | Bwn-gy c-f SAND, and Gravel, little Silt | | | | | | 62 |
| 4 | | 31 | | | | | | | | | | | | |
| 5 | 50+ | 50/4 | S-3 | 6 | | M | SM | Bwn-gy c-f SAND, little c-f Gravel, little Silt | | | | | | 160.5 |
| 6 | | 48 | | | | | | Drilled through cobble/boulder obstruction to 8' | | | | | | |
| 7 | | 50/1 | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | |
| 9 | 45 | 20 | S-4 | 17 | | W | SM | Gy c-f SAND, some c-f Gravel, little Silt | | | | | | 155.5 |
| 10 | | 17 | | | | | | | | | | | | |
| 11 | 79 | 28 | S-5 | 13 | | W | SM | Bwn c-f SAND, little c-f Gravel, little Silt | | | | | | 79 |
| 12 | | 30 | | | | | | | | | | | | |
| 13 | | 18 | | | | | | Drilled through cobble/boulder obstruction to 15' | | | | | | |
| 14 | | 29 | | | | | | | | | | | | |
| 15 | | 50 | | | | | | | | | | | | 150.5 |
| 16 | 88+ | 50/3 | S-6 | | | W | GM | Bwn-gy c-f GRAVEL, and Sand, little Silt | | | | | | 88 |
| 17 | | 40 | | | | | | | | | | | | |
| 18 | | 38 | | | | | | | | | | | | |
| 19 | | 50/1 | | | | | | | | | | | | |
| 20 | 50+ | 50/0 | | | | | | Split spoon sampler refusal @ 20' Drilled to 22' Auger refusal at 22' | | | | | | 145.5 |
| 21 | | | | | | | | | | | | | | |
| 22 | | | | | | | | End of Boring at 22' | | | | | | |
| 23 | | | | | | | | | | | | | | |
| 24 | | | | | | | | | | | | | | |
| 25 | | | | | | | | | | | | | | 140.5 |
| 26 | | | | | | | | | | | | | | |
| 27 | | | | | | | | | | | | | | |

BORING LOG 12117.01.GPJ, TECTONIC ENG.GDT, 8/25/23

REMARKS: Surface elevations estimated based on the NEI Survey, dated August 9, 2023, and reference NAVD 88.



PROJECT No. 12117.01
 PROJECT: URI Radio Tower System
 LOCATION: 875 Plains Rd, South Kingstown, RI

BORING No. B-2

SHEET No. 1 of 1

| | | | | | | |
|---|--------|--------------|---------------------------------|---|---|----------------------------|
| CLIENT: URI | | GROUND WATER | DATE | TIME | DEPTH | INSPECTOR: Connor McCleary |
| CONTRACTOR: Geo Logic - Earth Exploration, Inc. | | | | | | DRILLER: Damien Jacobs |
| METHOD OF ADVANCING BORING | DIA. | DEPTH | | | SURFACE ELEVATION: 175.0 | |
| POWER AUGER: | | TO | MON. WELL | <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO | DATUM: See Remarks | |
| ROT. DRILL: | 2 7/8" | 0 TO 15' | SCREEN DEPTH: -- TO -- | | DATE START: 7/19/23 | |
| CASING: | 4" | 0 TO 15' | WEATHER: Clear TEMP: 80° F | | DATE FINISH: 7/19/23 | |
| DIAMOND CORE: | | TO | DEPTH TO ROCK: Not Encountered' | | UNCONFINED COMPRESS. STRENGTH (TONS/FT) | |
| Acker Rebel Track Rig with Automatic Hammer | | | *CHANGES IN STRATA ARE INFERRED | | | |

| DEPTH (FT.) | N OR MIN./FT. | PENETRATION RESISTANCE (BLU/6 IN.) | SAMPLES | | | MOISTURE | UNIFIED SOIL CLASS. | DESCRIPTION OF MATERIAL | LITHOLOGY* | UNCONFINED COMPRESS. STRENGTH (TONS/FT) | | | | | ELEVATION (FT.) | |
|-------------|---------------|------------------------------------|---------------|---------------------|---------|----------|---------------------|--|------------|---|---|---|---|---|-----------------|-------|
| | | | SAMPLE NUMBER | RECOV. LENGTH (IN.) | RQD (%) | | | | | 1 | 2 | 3 | 4 | 5 | | |
| 1 | 50+ | 9 50/3 | S-1 | 8 | | M | SM | Bwn c-f SAND, little c-f Gravel, little Silt, trace Organics | | | | | | | | |
| 2 | | | | | | | | Drilled through cobble/boulder obstruction to 4' | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | |
| 5 | 40 | 9 20 20 | S-2 | 15 | | M | SM | Gy c-f SAND, some Silt, little f Gravel | | | | | | | | 170.0 |
| 6 | | 18 | | | | | | | | | | | | | | |
| 7 | 50+ | 15 50/1 | S-3 | 4 | | M | GM | Gy-bwn c-f GRAVEL, and c-f Sand, little Silt | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | |
| 9 | 97+ | 19 47 50/2 | S-4 | 14 | | W | SM | Bwn c-f SAND, little c-f Gravel, little Silt | | | | | | | | 97 |
| 10 | | | | | | | | | | | | | | | | 165.0 |
| 11 | | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | |
| 13 | | | | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | | | | 160.0 |
| 16 | 50+ | 14 50/6 | S-5 | 12 | | W | SM | Bwn c SAND, trace Gravel, little Silt Drilled to 17'. Auger refusal at 17'. | | | | | | | | |
| 17 | | | | | | | | | | | | | | | | |
| 18 | | | | | | | | End of Boring at 17' | | | | | | | | |
| 19 | | | | | | | | | | | | | | | | |
| 20 | | | | | | | | | | | | | | | | 155.0 |
| 21 | | | | | | | | | | | | | | | | |
| 22 | | | | | | | | | | | | | | | | |
| 23 | | | | | | | | | | | | | | | | |
| 24 | | | | | | | | | | | | | | | | |
| 25 | | | | | | | | | | | | | | | | 150.0 |
| 26 | | | | | | | | | | | | | | | | |
| 27 | | | | | | | | | | | | | | | | |

BORING LOG 12117.01.GPJ TECTONIC ENG.GDT 8/25/23

REMARKS: Surface elevations estimated based on the NEI Survey, dated August 9, 2023, and reference NAVD 88.



PROJECT No. 12117.01
 PROJECT: URI Radio Tower System
 LOCATION: 875 Plains Rd, South Kingstown, RI

BORING No. B-3

SHEET No. 1 of 1

| | | | | | | | | |
|---|--------|----------|---------------------------------|------------------------------|--|-------|---|--|
| CLIENT: URI | | | GROUND WATER | DATE | TIME | DEPTH | INSPECTOR: Connor McCleary | |
| CONTRACTOR: Geo Logic - Earth Exploration, Inc. | | | | | | | DRILLER: Damien Jacobs | |
| METHOD OF ADVANCING BORING | DIA. | DEPTH | | | | | SURFACE ELEVATION: 166.0 | |
| POWER AUGER: | | TO | MON. WELL | <input type="checkbox"/> YES | <input checked="" type="checkbox"/> NO | | DATUM: See Remarks | |
| ROT. DRILL: | 2 7/8" | 0 TO 20' | SCREEN DEPTH: | -- | TO -- | | DATE START: 7/19/23 | |
| CASING: | 4" | 0 TO 20' | WEATHER: Clear | | TEMP: 80° F | | DATE FINISH: 7/19/23 | |
| DIAMOND CORE: | | TO | DEPTH TO ROCK: Not Encountered' | | | | UNCONFINED COMPRESS. STRENGTH (TONS/FT) | |
| Acker Rebel Track Rig with Automatic Hammer | | | *CHANGES IN STRATA ARE INFERRED | | | | | |

| DEPTH (FT.) | N OR MIN./FT. | PENETRATION RESISTANCE (BL/6 IN.) | SAMPLES | | | UNIFIED SOIL CLASS. | DESCRIPTION OF MATERIAL | LITHOLOGY* | UNCONFINED COMPRESS. STRENGTH (TONS/FT) | | | ELEVATION (FT.) | | |
|-------------|---------------|-----------------------------------|---------------|---------------------|----------------|---------------------|-------------------------|---|---|---|---|-----------------|---|-------|
| | | | SAMPLE NUMBER | RECOV. LENGTH (IN.) | RECOV. RQD (%) | | | | MOISTURE | 1 | 2 | | 3 | 4 |
| 1 | 4 | 2 2 2 | S-1 | 14 | | M | SM | Bwn c-f SAND, little c-f Gravel, little Silt | | | | | | |
| 2 | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | |
| 5 | 46 | 21 24 22 | S-2 | 16 | | M | SM | Bwn c-f SAND, little c-f Gravel, little Silt | | | | | | 161.0 |
| 6 | | 20 | | | | | | Drilled through cobble/boulder obstruction to 8' | | | | | | |
| 7 | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | |
| 9 | 50+ | 48 50/3 | S-3 | 9 | | W | SM | Gy-blk c-f SAND, some f Gravel, little Silt | | | | | | 156.0 |
| 10 | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | |
| 13 | | | | | | | | Drilled through cobble/boulder obstruction to 15' | | | | | | |
| 14 | | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | | 151.0 |
| 16 | 50+ | 45 50/4 | S-4 | 7 | | W | SM | Gy c-f SAND, little c-f Gravel, little Silt | | | | | | |
| 17 | | | | | | | | | | | | | | |
| 18 | | | | | | | | Drilled through cobble/boulder obstruction to 20' | | | | | | |
| 19 | | | | | | | | | | | | | | |
| 20 | 50+ | 50/5 | S-5 | 8 | | W | SM | Same | | | | | | 146.0 |
| 21 | | | | | | | | Drilled to 21' Auger refusal at 21' | | | | | | |
| 22 | | | | | | | | End of Boring at 21' | | | | | | |
| 23 | | | | | | | | | | | | | | |
| 24 | | | | | | | | | | | | | | |
| 25 | | | | | | | | | | | | | | 141.0 |
| 26 | | | | | | | | | | | | | | |
| 27 | | | | | | | | | | | | | | |

BORING LOG 12117.01.GPJ TECTONIC ENG.GDT 8/25/23

REMARKS: Surface elevations estimated based on the NEI Survey, dated August 9, 2023, and reference NAVD 88.



PROJECT No. 12117.01
 PROJECT: URI Radio Tower System
 LOCATION: 875 Plains Rd, South Kingstown, RI

BORING No. B-4
 SHEET No. 1 of 1

| | | | | | |
|---|--------------|----------|---|-------|---|
| CLIENT: URI | GROUND WATER | DATE | TIME | DEPTH | INSPECTOR: Connor McCleary |
| CONTRACTOR: Geo Logic - Earth Exploration, Inc. | | | | | DRILLER: Damien Jacobs |
| METHOD OF ADVANCING BORING | DIA. | DEPTH | | | SURFACE ELEVATION: 147.0 |
| POWER AUGER: | | TO | MON. WELL <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO | | DATUM: See Remarks |
| ROT. DRILL: | 2 7/8" | 0 TO 15' | SCREEN DEPTH: -- TO -- | | DATE START: 7/20/23 |
| CASING: | 4" | 0 TO 15' | WEATHER: Clear TEMP: 80° F | | DATE FINISH: 7/20/23 |
| DIAMOND CORE: | | TO | DEPTH TO ROCK: Not Encountered' | | UNCONFINED COMPRESS. STRENGTH (TONS/FT) |
| Acker Rebel Track Rig with Automatic Hammer | | | *CHANGES IN STRATA ARE INFERRED | | 1 2 3 4 5 |

| DEPTH (FT.) | N OR MIN./FT. | PENETRATION RESISTANCE (BL/6 IN.) | SAMPLES | | | UNIFIED SOIL CLASS. | DESCRIPTION OF MATERIAL | LITHOLOGY* | UNCONFINED COMPRESS. STRENGTH (TONS/FT) | | | ELEVATION (FT.) |
|-------------|---------------|-----------------------------------|---------------|---------------------|---------|---------------------|-------------------------|--|---|-----------------|-----------------|-----------------|
| | | | SAMPLE NUMBER | RECOV. LENGTH (IN.) | RQD (%) | | | | MOISTURE | PLASTIC LIMIT % | WATER CONTENT % | |
| 1 | 10 | 3 | S-1 | 22 | | M | SM | Bwn-gy c-f SAND, little f Gravel, little Silt | | | | |
| 2 | | 4 | | | | | | | | | | |
| 3 | 33 | 12 | S-2 | 18 | | M | SM | Same | | | | |
| 4 | | 13 | | | | | | | | | | |
| 5 | 70+ | 20 | S-3 | 11 | | M | SM | Bwn-tn c-f SAND, little c-f Gravel, little Silt | | | | 142.0 |
| 6 | | 50/5 | | | | | | | | | | |
| 7 | 50 | 17 | S-4 | 17 | | W | SM | Bwn-gy c-f Sand, and c-f Gravel, little Silt | | | | |
| 8 | | 22 | | | | | | | | | | |
| 9 | 32 | 11 | S-5 | 15 | | W | GM | Gy-bwn c-f GRAVEL, little c-f Sand, little Silt | | | | 137.0 |
| 10 | | 14 | | | | | | | | | | |
| 11 | | 18 | | | | | | | | | | |
| 12 | | 18 | | | | | | | | | | |
| 13 | | 11 | | | | | | | | | | |
| 14 | | 14 | | | | | | | | | | |
| 15 | 50+ | 50/0 | S-6 | 0 | | | | No Recovery Drilled to 15' Auger refusal at 15' | | | | 132.0 |
| 16 | | | | | | | | | | | | |
| 17 | | | | | | | | End of Boring at 15' | | | | |
| 18 | | | | | | | | | | | | |
| 19 | | | | | | | | | | | | |
| 20 | | | | | | | | | | | | 127.0 |
| 21 | | | | | | | | | | | | |
| 22 | | | | | | | | | | | | |
| 23 | | | | | | | | | | | | |
| 24 | | | | | | | | | | | | |
| 25 | | | | | | | | | | | | 122.0 |
| 26 | | | | | | | | | | | | |
| 27 | | | | | | | | | | | | |

REMARKS: Surface elevations estimated based on the NEI Survey, dated August 9, 2023, and reference NAVD 88.

BORING LOG 12117.01.GPJ TECTONIC ENG.GDT 8/25/23

LEGEND FOR SOIL DESCRIPTION

| | |
|---|---|
| <u>COARSE GRAINED SOIL</u> (Coarser than No. 200 Sieve) | |
| <u>DESCRIPTIVE TERM & GRAIN SIZE</u> | |
| <u>TERM</u> | <u>SAND</u> <u>GRAVEL</u> |
| coarse - c | No. 4 Sieve to No. 10 Sieve 3" to 3/4" |
| medium - m | No. 10 Sieve to No. 40 Sieve 3/4" to 3/16" |
| fine - f | No. 40 Sieve to No. 200 Sieve |
| <u>COBBLES</u> 3" to 10" | <u>BOULDERS</u> 10" + |
| <u>GRADATION DESIGNATIONS</u> | <u>PROPORTIONS OF COMPONENT</u> |
| fine, f | Less than 10% coarse to medium |
| medium to fine, m-f | Less than 10% coarse |
| medium, m | Less than 10% coarse and fine |
| coarse to medium, c-m | Less than 10% fine |
| coarse, c | Less than 10% medium and fine |
| coarse to fine, c-f | All greater than 10% |
| <u>FINE GRAINED SOIL</u> (Finer than No. 200 Sieve) | |
| <u>DESCRIPTION</u> | <u>PLASTICITY INDEX</u> <u>PLASTICITY</u> |
| Silt | 0 - 1 none |
| Clayey Silt | 2 - 5 slight |
| Silt & Clay | 6 - 10 low |
| Clay & Silt | 11 - 20 medium |
| Silty Clay | 21 - 40 high |
| Clay | greater than 40 very high |
| <u>PROPORTION</u> | |
| <u>DESCRIPTIVE TERM</u> | <u>PERCENT OF SAMPLE WEIGHT</u> |
| trace | 1 - 10 |
| little | 10 - 20 |
| some | 20 - 35 |
| and | 35 - 50 |
| The primary component is fully capitalized if >50% of sample | |
| <u>COLOR</u> | |
| Blue - blue | Gy - gray Wh - white |
| Blk - black | Or - orange Yl - yellow |
| Bwn - brown | Rd - red Lgt - light |
| Gn - green | Tn - tan Dk - dark |
| <u>SAMPLE NOTATION</u> | |
| S - Split Spoon Soil Sample | WOC - Weight of Casing |
| U - Undisturbed Tube Sample | WOR - Weight of Rods |
| C - Core Sample | WOH - Weight of Hammer |
| B - Bulk Soil Sample | PPR - Compressive Strength based on Pocket Penetrometer |
| NR - No Recovery of Sample | TV - Shear Strength (tsf) based on Torvane |
| <u>ADDITIONAL CLASSIFICATIONS</u> | |
| New York City Building Code soil classifications are given in parentheses at the end of each description of material, if applicable. See sections 1804.2 of the 2008 Building Code for further details. | |



SOIL RESISTIVITY DATA SHEET

W.O.#: 12117.01 PAGE 1 of 2
PROJECT: URI Radio Tower System
LOCATION: Rhode Island

CLIENT: URI DATE: 7/19/2023 INSPECTOR: Connor McCleary
CONTRACTOR: Tectonic Weather / Temp. (F): Clear / 75 SURFACE ELEVATION:

LOCATION OF TEST: R-1 DATUM:


EQUIPMENT: AEMC Instruments Model 6472 Digital Ground Resistance Tester

| Electrode Spacing "a" (ft) | Resistance (Ω) | Electrode Depth "a/20" (in) | Resistivity ($\Omega \cdot \text{cm}$) |
|----------------------------|-------------------------|-----------------------------|--|
| 2.5 | 459.0 | 6 | 219759 |
| 5 | 319.0 | 6 | 305461 |
| 10 | 165 | 6 | 315994 |
| 20 | 65.3 | 6 | 250114 |
| 35 | 37.60 | 6 | 252029 |
| OTHER | | | |
| OTHER | | | |

Orientation of leads:

Topography:

Remarks:



ADDITIONAL NOTES:

Wenner Four Point method



SOIL RESISTIVITY
DATA SHEET

W.O.#: 12117.01 | PAGE 2 of 2

PROJECT: URI Radio Tower System

LOCATION: Rhode Island

INSPECTOR: Connor McCleary

CLIENT: URI

DATE: 7/19/2023

Weather / Temp. (F): Clear / 75

SURFACE ELEVATION:

CONTRACTOR: Tectonic

LOCATION OF TEST: R-2

DATUM:


EQUIPMENT: AEMC Instruments Model 6472 Digital Ground Resistance Tester

| Electrode Spacing "a" (ft) | Resistance (Ω) | Electrode Depth "a/20" (in) | Resistivity ($\Omega \cdot \text{cm}$) |
|----------------------------|-------------------------|-----------------------------|--|
| 2.5 | 436.0 | 6 | 208747 |
| 5 | 310.0 | 6 | 296843 |
| 10 | 185 | 6 | 354296 |
| 20 | 71.9 | 6 | 275393 |
| 35 | 40.10 | 6 | 268786 |
| OTHER | | | |
| OTHER | | | |

Orientation of leads:


Topography:

Remarks:



ADDITIONAL NOTES:

Wenner Four Point method



| | | | | | | |
|---------|--------|------|--------|--------|------|--------------|
| COBBLES | GRAVEL | | SAND | | | SILT OR CLAY |
| | coarse | fine | coarse | medium | fine | |

| Sample Identification | Classification | | | | | WC% | LL | PL | PI | Cc | Cu |
|-----------------------|---|--|--|--|--|------|----|----|----|----|----|
| ● B-1 0.0 S-1 | Bwn-Gy Silt, and c-f Sand, little f Gravel | | | | | 19.9 | | | | | |
| ☒ B-1 8.0 S-4 | Gy c-f SAND, some c-f Gravel, little Silt | | | | | 8.9 | | | | | |
| ▲ B-2 4.0 S-2 | Gy c-f SAND, some Silt, little f Gravel | | | | | 9.4 | | | | | |
| ★ B-3 8.0 S-3 | Gy-Blk c-f SAND, some f Gravel, little Silt | | | | | 10.9 | | | | | |
| ⊙ B-4 2.0 S-2 | Bwn-Gy c-f SAND, little f Gravel, little Silt | | | | | 6.1 | | | | | |

| Sample Identification | D100 | D60 | D30 | D10 | %Gravel | %Sand | %Silt | %Clay | Source of Material |
|-----------------------|------|-------|-------|-----|---------|-------|-------|-------|--------------------|
| ● B-1 0.0 S-1 | 9.5 | 0.213 | | | 11.6 | 42.9 | 45.4 | | Boring |
| ☒ B-1 8.0 S-4 | 37.5 | 0.953 | 0.161 | | 20.8 | 60.4 | 18.9 | | Boring |
| ▲ B-2 4.0 S-2 | 9.5 | 0.633 | 0.122 | | 16.9 | 61.2 | 22.0 | | Boring |
| ★ B-3 8.0 S-3 | 9.5 | 2 | 0.173 | | 29.2 | 52.7 | 18.1 | | Boring |
| ⊙ B-4 2.0 S-2 | 9.5 | 0.76 | 0.163 | | 18.5 | 64.7 | 16.8 | | Boring |

Tectonic


280 Little Britain Road, Bldg. 2
Newburgh, NY 12550
Telephone: (845) 563-9081

Fax: (845) 563-9085

GRAIN SIZE DISTRIBUTION

Project No: 12117.01 Date: 8/9/23
Project: URI Radio Tower System
Location: Kingston, Rhode Island

GRAIN SIZE DISTRIBUTION 12117.01.GPJ TECTONIC ENG.GDT 8/9/23



| COBBLES | GRAVEL | | SAND | | | SILT OR CLAY |
|---------|--------|------|--------|--------|------|--------------|
| | coarse | fine | coarse | medium | fine | |

| Sample Identification | Classification | | | | | WC% | LL | PL | PI | Cc | Cu |
|-----------------------|--|--|--|--|--|-----|----|----|----|----|----|
| ● B-4 6.0 S-4 | Bwn-Gy c-f Sand, and c-f Gravel, little Silt | | | | | 9.5 | | | | | |

| Sample Identification | D100 | D60 | D30 | D10 | %Gravel | %Sand | %Silt | %Clay | Source of Material |
|-----------------------|------|------|-------|-----|---------|-------|-------|-------|--------------------|
| ● B-4 6.0 S-4 | 37.5 | 2.57 | 0.226 | | 35.8 | 47.5 | 16.7 | | Boring |

GRAIN SIZE DISTRIBUTION 12117.01.GPJ, TECTONIC ENG.GDT, 8/9/23



280 Little Britain Road, Bldg. 2
 Newburgh, NY 12550
 Telephone: (845) 563-9081

Fax: (845) 563-9085

GRAIN SIZE DISTRIBUTION

Project No: 12117.01 Date: 8/9/23
 Project: URI Radio Tower System
 Location: Kingston, Rhode Island



Wednesday, August 09, 2023

Attn: Chris Ferri
Tectonic Engineering
70 Pleasant Hill Road
Mountainville, NY 10953

Project ID: 12117.01 URI RADIO TOWER SYSTEM
SDG ID: GCO67701
Sample ID#s: CO67701 - CO67702

This laboratory is in compliance with the NELAC requirements of procedures used except where indicated.

This report contains results for the parameters tested, under the sampling conditions described on the Chain Of Custody, as received by the laboratory. This report is incomplete unless all pages indicated in the pagination at the bottom of the page are included.

All soils, solids and sludges are reported on a dry weight basis unless otherwise noted in the sample comments.

A scanned version of the COC form accompanies the analytical report and is an exact duplicate of the original.

If you are the client above and have any questions concerning this testing, please do not hesitate to contact Phoenix Client Services at ext.200. The contents of this report cannot be discussed with anyone other than the client listed above without their written consent.

Sincerely yours,

A handwritten signature in cursive script that reads "Phyllis Shiller".

Phyllis Shiller
Laboratory Director

NELAC - #NY11301
CT Lab Registration #PH-0618
MA Lab Registration #M-CT007
ME Lab Registration #CT-007
NH Lab Registration #213693-A,B

NJ Lab Registration #CT-003
NY Lab Registration #11301
PA Lab Registration #68-03530
RI Lab Registration #63
VT Lab Registration #VT11301



Environmental Laboratories, Inc.
587 East Middle Turnpike, P.O.Box 370, Manchester, CT 06045
Tel. (860) 645-1102 Fax (860) 645-0823

Sample Id Cross Reference

August 09, 2023

SDG I.D.: GCO67701

Project ID: 12117.01 URI RADIO TOWER SYSTEM

| Client Id | Lab Id | Matrix |
|-----------------------|---------|--------|
| COMPOSITE: TOWER BASE | CO67701 | SOIL |
| COMPOSITE: DEADMAN | CO67702 | SOIL |



Environmental Laboratories, Inc.
 587 East Middle Turnpike, P.O.Box 370, Manchester, CT 06045
 Tel. (860) 645-1102 Fax (860) 645-0823

Analysis Report
 August 09, 2023

FOR: Attn: Chris Ferri
 Tectonic Engineering
 70 Pleasant Hill Road
 Mountainville, NY 10953

Sample Information

Matrix: SOIL
 Location Code: TECTONIC
 Rush Request: Standard
 P.O.#: 12117.01

Custody Information

Collected by:
 Received by: SR1
 Analyzed by: see "By" below

Date Time

07/20/23 9:00
 08/07/23 16:06

Laboratory Data

SDG ID: GCO67701
 Phoenix ID: CO67701

Project ID: 12117.01 URI RADIO TOWER SYSTEM
 Client ID: COMPOSITE: TOWER BASE

| Parameter | Result | RL/ PQL | Units | Dilution | Date/Time | By | Reference |
|------------------|----------|------------|----------|----------|----------------|-------|--------------|
| Percent Solid | 91 | | % | | 08/07/23 | CV | SW846-%Solid |
| Chloride | < 55 | 55 | mg/kg | 10 | 08/07/23 | BS/GD | SW9056A |
| Corrosivity | Negative | | Pos/Neg | 1 | 08/08/23 | MW/ER | SW846-Corr |
| pH at 25C - Soil | 6.60 | 1.00 | pH Units | 1 | 08/08/23 00:04 | MW/ER | SW846 9045D |
| Sulfate | < 55 | 55 | mg/kg | 10 | 08/07/23 | BS/GD | SW9056A |

RL/PQL=Reporting/Practical Quantitation Level ND=Not Detected BRL=Below Reporting Level

Comments:

The regulatory hold time for pH is immediately. This pH was performed in the laboratory and may be considered outside of hold-time.

Corrosivity is based solely on the pH analysis performed above.

All soils, solids and sludges are reported on a dry weight basis unless otherwise noted in the sample comments.

If you are the client above and have any questions concerning this testing, please do not hesitate to contact Phoenix Client Services at ext.200. The contents of this report cannot be discussed with anyone other than the client listed above without their written consent.

Phyllis Shiller, Laboratory Director

August 09, 2023

Reviewed and Released by: Anil Makol, Project Manager



Environmental Laboratories, Inc.
 587 East Middle Turnpike, P.O.Box 370, Manchester, CT 06045
 Tel. (860) 645-1102 Fax (860) 645-0823

Analysis Report
 August 09, 2023

FOR: Attn: Chris Ferri
 Tectonic Engineering
 70 Pleasant Hill Road
 Mountainville, NY 10953

Sample Information

Matrix: SOIL
 Location Code: TECTONIC
 Rush Request: Standard
 P.O.#: 12117.01

Custody Information

Collected by:
 Received by: SR1
 Analyzed by: see "By" below

Date Time

07/20/23 9:00
 08/07/23 16:06

Laboratory Data

SDG ID: GCO67701
 Phoenix ID: CO67702

Project ID: 12117.01 URI RADIO TOWER SYSTEM
 Client ID: COMPOSITE: DEADMAN

| Parameter | Result | RL/ PQL | Units | Dilution | Date/Time | By | Reference |
|------------------|----------|------------|----------|----------|----------------|-------|--------------|
| Percent Solid | 93 | | % | | 08/07/23 | CV | SW846-%Solid |
| Chloride | < 54 | 54 | mg/kg | 10 | 08/07/23 | BS/GD | SW9056A |
| Corrosivity | Negative | | Pos/Neg | 1 | 08/08/23 | MW/ER | SW846-Corr |
| pH at 25C - Soil | 6.26 | 1.00 | pH Units | 1 | 08/08/23 00:04 | MW/ER | SW846 9045D |
| Sulfate | < 54 | 54 | mg/kg | 10 | 08/07/23 | BS/GD | SW9056A |

RL/PQL=Reporting/Practical Quantitation Level ND=Not Detected BRL=Below Reporting Level

Comments:

The regulatory hold time for pH is immediately. This pH was performed in the laboratory and may be considered outside of hold-time.

Corrosivity is based solely on the pH analysis performed above.

All soils, solids and sludges are reported on a dry weight basis unless otherwise noted in the sample comments.

If you are the client above and have any questions concerning this testing, please do not hesitate to contact Phoenix Client Services at ext.200. The contents of this report cannot be discussed with anyone other than the client listed above without their written consent.

Phyllis Shiller, Laboratory Director

August 09, 2023

Reviewed and Released by: Anil Makol, Project Manager



Environmental Laboratories, Inc.
 587 East Middle Turnpike, P.O.Box 370, Manchester, CT 06045
 Tel. (860) 645-1102

QA/QC Report

August 09, 2023

QA/QC Data

SDG I.D.: GCO67701

| Parameter | Blk | Sample | Dup | Dup | LCS | LCSD | LCS | MS | MSD | MS | % | % |
|---|-------|--------|--------|--------|------|------|-----|-----|-----|-----|----------|--------|
| | Blank | RL | Result | Result | RPD | % | % | RPD | % | RPD | Rec | RPD |
| | | | | | | | | | | | Limits | Limits |
| QA/QC Batch 691117 (PH), QC Sample No: CO67445 (CO67701, CO67702) | | | | | | | | | | | | |
| pH | | | 6.71 | 6.76 | 0.70 | 101 | | | | | 85 - 115 | 20 |
| QA/QC Batch 691171 (mg/L), QC Sample No: CO67384 (CO67701, CO67702) | | | | | | | | | | | | |
| Chloride | BRL | 5.0 | 6.7 | 6.7 | NC | 95.0 | | 104 | | | 90 - 110 | 20 |
| Sulfate | BRL | 5.0 | <5.0 | <5.0 | NC | 99.7 | | 112 | | | 90 - 110 | 20 |

m = This parameter is outside laboratory MS/MSD specified recovery limits.

If there are any questions regarding this data, please call Phoenix Client Services at extension 200.

RPD - Relative Percent Difference

LCS - Laboratory Control Sample

LCSD - Laboratory Control Sample Duplicate

MS - Matrix Spike

MS Dup - Matrix Spike Duplicate

NC - No Criteria

Intf - Interference

Phyllis Shiller, Laboratory Director
 August 09, 2023

Wednesday, August 09, 2023

Criteria: None

State: RI

Sample Criteria Exceedances Report

GCO67701 - TECTONIC

| SampNo | Acode | Phoenix Analyte | Criteria | Result | RL | Criteria | RL Criteria | Analysis Units |
|--------|-------|-----------------|----------|--------|----|----------|----------------|-------------------|
|--------|-------|-----------------|----------|--------|----|----------|----------------|-------------------|

*** No Data to Display ***

Phoenix Laboratories does not assume responsibility for the data contained in this exceedance report. It is provided as an additional tool to identify requested criteria exceedances. All efforts are made to ensure the accuracy of the data (obtained from appropriate agencies). A lack of exceedance information does not necessarily suggest conformance to the criteria. It is ultimately the site professional's responsibility to determine appropriate compliance.



Environmental Laboratories, Inc.
587 East Middle Turnpike, P.O.Box 370, Manchester, CT 06045
Tel. (860) 645-1102 Fax (860) 645-0823



Analysis Comments

August 09, 2023

SDG I.D.: GCO67701

The following analysis comments are made regarding exceptions to criteria not already noted in the Analysis Report or QA/QC Report: None.

Our Story

For the past 30 years, Tectonic has delivered quality professional services in a timely and cost effective manner by pooling its talented staff into project teams that think, act, and perform as one integral unit. By carefully listening and collaborating with its clients, the firm is able to identify the key issues and ensure stakeholder objectives are met in the final deliverables. Through innovating and adopting technological advances, the firm is able to generate unique solutions to improve our industry, strengthening infrastructure and build safe sustainable communities.

As the world evolves, and its challenges grow more complex, Tectonic continues to innovate and provide the practical solutions and exceptional customer service its clients have noticed since its founding.

www.TectonicEngineering.com

Tectonic

MOUNTAINVILLE, NY (CORPORATE OFFICE)
70 Pleasant Hill Road, PO Box 37
Mountainville, NY, 10953
Phone: 845-534-5959
Fax: 845-534-5993

W. Moratti

BASIC LAYOUT - WALLS AND DOORS
FOR WR1U TRANSMITTER BLDG

NEW WALLS MUST CONFORM
TO NORMAL (HOUSE)
CONSTRUCTION STANDARDS -
IE. SHOULD BE THERMALLY
INSULATED TO R-11 AND
SECURE AGAINST EASY
BREAK-IN.

NEW WALL

12'

DOOR SIZE 84" X 36"

EXISTING DOOR

NEW WALL

NEW WALL:
BUILT OUT TO
EXISTING DOOR -
APPROXIMATELY 9'

DOOR SIZE
84" X 36"
(MUST HAVE DEAD
BOLT LOCK)

WORK BENCH:
3/4 PLYWOOD OR 5/8 PARTICLES
BOARD TOP 32" OFF FLOOR
MUST BE ABLE TO SUPPORT
200 to 300 lbs.

60"

(2x4
FRAME)

36"

WR1U TRANSMITTER BLDG

SCALE: NONE

4/29/81

KMT

BIG-GRIPS (DEAD END) COMPLETE WITH END SLEEVE

| <u>PART NUMBER</u> | | <u>WT.</u> |
|--------------------|--|------------|
| | <u>FOR 7-STRAND GALVANIZED GUY WIRE</u> | |
| BG2142 | 3/16" Big-Grip, 23" length, complete with GC65303 end sleeve | 28/100 |
| BG2144 | 1/4" Big-Grip, 27" length, complete with GC65136 end sleeve | 38/100 |
| BG2146 | 5/16" Big-Grip, 33" length, complete with GC65128 end sleeve | 66/100 |
| *BG2147 | 3/8" Big-Grip, 37" length, complete with GC65264 end sleeve | 95/100 |
| *BG2148 | 7/16" Big-Grip, 40" length, complete with GC65265 end sleeve | 140/100 |
| *BG2115 | 1/2" Big-Grip, 50" length, complete with GC65266 end sleeve | 229/100 |
| *BG2116 | 9/16" Big-Grip, 55" length, complete with GC65267 end sleeve | 342/100 |
| *BG2111 | 5/8" Big-Grip, 64" length, complete with GC65268 end sleeve | 355/100 |

FOR 19-STRAND GALVANIZED GUY WIRE

| | | |
|---------|---|----------|
| *BG2112 | 3/4" Big-Grip, 76" length, complete with GC65269 end sleeve | 1080/100 |
|---------|---|----------|

NOTE: 1) End sleeves must be used on all Big-Grips. See Drawing B-700607 for procedure to apply end sleeve on Big-Grips.


2) Oversized heavy duty thimbles must be used with all Big-Grips.

*Prices available upon request.

Refer to alphabetical/numerical price list for current prices on other items.



F. O. B. PEORIA, ILLINOIS

SPECIFICATIONS SUBJECT TO CHANGE WITHOUT NOTICE.




BASE GROUNDING KITS (BGK OR BGKE)

NOTE:
REMOVE ALL SHARP BENDS FROM COPPER WIRE



ANCHOR GROUNDING KITS


| | | | |
|--|-------------|--|----------|
| R. 1-20 CAMP. P.O. BOX 4486 KEOKUK IA 50240 | | 6-9-79 | |
| NO. | DESCRIPTION | DATE | BY |
| REVISIONS | | | |
| ROHN MANUFACTURING | | | |
| DIVISION OF | | | |
| TITLE TOWER GROUNDING METHODS | | | |
| THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT. | | | FILE NO. |
| DESIGN | DRAWN | CHECKED | DATE |
| NONE | | | |
| REV. BY | DATE | REVISED DIMENSIONS SPECIFIED ARE GIVEN IN INCHES | |
| VER | 11-20-73 | | |
| REV. BY | DATE | VOLUNTEER | DWG. NO. |
| VER | 11-20-73 | | |
| REV. BY | DATE | REV. PAGE | SHEET |
| VER | 7-10-73 | 1 | 1 |
| REV. BY | DATE | | |
| VER | 12/1/73 | | |
| | | | C-731105 |



| BILL OF MATERIAL | | | | |
|------------------|-------|-----------|------------------|-------------|
| ITEM | QUAN. | PART. NO. | DESCRIPTION | DWG. NO. |
| 1 | 3 | B 65G | GUY BRACKET | C 670701 R4 |
| 2 | 3 | JR 810 A | 1/2" U-BOLT ASSY | 965/028 R19 |
| 3 | 3 | JA 655 A | 1/2" U-BOLT ASSY | B710909 R3 |
| 4 | 3 | 1/2 S | 1/2" SHACKLES | --- |

NOTE: UPPER U-BOLT OF BRACKET MUST INTERCONNECT WITH "ZIG-ZAG" BRACE AS SHOWN.

NOTE: BRACKET DESIGNED FOR USE WITH A MAXIMUM OF 7/8" EHS GUY STRAND.



R1 ADDED ITEM #5 REDUCED ITEM #2 QUAN. 10-6-71 OH

| NO. | DESCRIPTION | DATE | BY |
|-----|-------------|------|----|
|-----|-------------|------|----|

ROHN

INSTALLATION INSTRUCTIONS
GAG5G GUYING ASSEMBLY

THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT.

| REV. | DESCRIPTION | DATE | BY | DATE | BY | FILE NO. |
|------|--------------------------------------|---------|-----|------|----|----------|
| R5 | UPDATED BILL OF MAT. & REN U-BOLT | 12-1-78 | KTL | | | |
| R4 | CORRECTED DWG. NO. | 6/29/76 | GLS | | | |
| R3 | REMOVED LOCKNUTS | 12/5/74 | DLH | | | |
| R2 | ADDED PAR. DWG. NOS. TO BILL OF MAT. | 1/18/72 | GLS | | | |

| DATE | MATERIAL | FINISH | HT. |
|------|----------|--------|-----|
| NONE | | | |

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE GIVEN IN INCHES

| DATE | BY | CHK | TRACES | SCALE | DWG. NO. |
|---------|------------|-----|--------|-------|-------------|
| 1-8-68 | A. JOHNSON | | | | |
| 1-16-68 | ck | | | | |
| 1-16-68 | RAK | | | | B 680104 R5 |

ASSEMBLY BOLT INSTALLATION:

All tower assembly bolts are to be inserted out and/or up (with nuts and pal nuts on the outside of tower face and top of flange connections) - unless prohibited by lack of clearance.


All assembly bolts are to be tightened according to E.I.A. Standard RS-222-B Subpart 1.1.5.2 - (where high strength galvanized bolts are used for nonfriction type connections, the bolts shall be tightened to a "snug tight" condition in accordance with "Specification for Structural Joints using A.S.T.M. A325 or A490 bolts").

Flat washers are to be installed with bolts over slotted holes.



CAUTION: Do not over-torque! Hot dipped galvanizing on bolts, nuts and steel parts tends to act as a lubricant, thus over-tightening can easily occur and can cause bolts to crack or snap off.

PAL NUT INSTALLATION:

Pal nuts are to be installed after nuts are tight and with edge lip out. (see picture below)




| No. ▲ | Revision | Description | ▲ Date | ▲ By |
|---|----------|---|--------|------|
| Unarco-Rohn Division of Unarco Industries, Inc. | | | | |
| Title <p style="text-align: center; font-size: 1.5em;"><i>BOLT ASSEMBLY INSTALLATION</i></p> | | | | |
| Scale | | NONE Unless otherwise specified, dimensions are given in inches. | | |
| Drawn by <i>Q.A.</i> | | Date 7-5-79 | | |
| Checked by <i>JAB</i> | | Date 7-5-79 | | |
| Approved by Engineering <i>TS</i> | | Date 7-5-79 | | |
| Approved by Production | | Date | | |
| Approved by Sales <i>PAK</i> | | Date 7-10-79 | | |
| File Number | | Drawing Number <p style="font-size: 1.5em;"><i>A 790135</i></p> | | |



DETAIL B
 NOTE: THIS SAFETY DEVICE INSTALLATION TO BE USED FOR ALL ROHN TOWERS USING EITHER A HEAVY OR STANDARD LADDER.

FABRICATION DRAWINGS
 (FOR SHOP USE ONLY)

- C 730517 R₃ - PARTS NO. BCB 1 & BCB 5
- B 740610 - PART NO. NH 13C
- SK 730903B - PART NO. CHC 1
- B 730650 R₆ - PART NO. 7L 01



DETAIL-A

NOTE: PAL NUTS PROVIDED FOR ALL BOLTS EXCEPT HAND GRIPS

| REV | ADD'D DETAIL B | 11/30 | RTG |
|---|----------------|---------|-------------------------|
| NO. | DESCRIPTION | DATE | BY |
| REVISIONS | | | |
| ROHN MANUFACTURING | | | |
| DIVISION OF | | | |
| TITLE ROHN-LOC INSTALLATION DETAILS | | | |
| for ROHN TOWERS w/LEG OR FACE MTD LADDER | | | |
| THIS DRAWING IS THE PROPERTY OF ROHN. IF IT IS NOT TO BE REPRODUCED, COPIED, OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT. | | | FILE NO. |
| DATE | DRAWN | CHECKED | IN CHARGE |
| 11-30-74 | WBL | WBL | WBL |
| DATE | BY | DATE | BY |
| 1-9-75 | WBL | 1-9-75 | WBL |
| DATE | BY | DATE | BY |
| 1-9-75 | WBL | 1-9-75 | WBL |
| UNLESS OTHERWISE SPECIFIED, DIMENSIONS ARE GIVEN IN INCHES. | | | DWG. NO. |
| | | | C 741170 R ₁ |

- 3/16 HS & EHS
- 1/4 HS & EHS
- 5/16 HS & EHS
- 3/8 HS & EHS
- 7/16 HS
- 1/2 HS
- 1/2 HS & EHS
- 9/16 HS
- 5/8 HS
- 3/4 EHS



3 CABLE CLAMPS REQ'D. PER TURNBACK

4 CABLE CLAMPS REQ'D. PER TURNBACK


5 CABLE CLAMPS REQ'D. PER TURNBACK

SERVE FREE (DEAD) END OF GUY AT EACH CONNECTION.

CABLE CLAMPS - SPACE CABLE CLAMPS 6 TIMES CABLE DIA. APART. (U-BOLT SHALL BEAR ON DEAD END)



NOTE: SEE DWG. NO. C 611211R3 FOR CABLE TENSIONING & TURNBUCKLE MAINTENANCE DETAILS.



NOTE: DUE TO VARIABLES INVOLVED IN ROOF AND OTHER INSTALLATIONS, IT SHALL BE THE CUSTOMER'S OR INSTALLER'S RESPONSIBILITY TO PROVIDE STRUCTURALLY ADEQUATE SUPPORTS FOR PIER & ANCHOR CONNECTIONS. IT MAY ALSO BE NECESSARY FOR THE CUSTOMER OR INSTALLER TO SECURE THE SERVICE OF A LOCAL ENGINEER TO DETERMINE THAT INSTALLATION COMPLIES WITH LOCAL BUILDING CODES.

| NO. | DESCRIPTION | DATE | BY |
|-----|--|----------|----|
| R1 | ADDED 3/4" EHS GUY WIRE | 9-15-87 | DA |
| R2 | ADDED NOTE | 5-8-78 | DA |
| R2 | ADDED NOTE | 7-23-75 | DA |
| R1 | ADDED CABLE CLAMPS REQ'D. PER GUY SIZE | 11-18-74 | DA |

REVISIONS

ROHN


TURBUCKLE SAFETY METHODS

THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT. FILE NO.

| | | | | |
|--------|------------|---------|---------|----|
| DESIGN | DRAWN | CHECKED | DATE | BY |
| NONE | A. JOHNSON | | 3-16-68 | |
| | DA | | 4-4-68 | |
| | DA | | | |

UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE GIVEN IN INCHES

| | |
|----------|----------|
| DWG. NO. | 8-680324 |
|----------|----------|



MATERIAL LAYOUT

LIGHTING KIT-CONDUIT-RA 3C

TOWER HEIGHTS 301'-450'
FAA-A-3

WIRING DIAGRAM

- PART NOS. FOR WIRE ABOVE:
 #14 TW (RED) - 530021
 #14 TW (WHITE) - 530022
 #10 TW (RED) - 530014
 #8 TW (BLACK) - 530009
 #8 TW (WHITE) - 530011
 #19 TW (BLACK) - 530024

* NIPPLE LENGTH TO BE DETERMINED BY TOWER FACE WIDTH

NOTE:

ALL CONNECTIONS SHOULD BE COMPLETELY TIGHT.

THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT.

| | | |
|-----------------------|---------------------------|-------------|
| DRAWN: HOFFMAN | 7/1/66 | CUSTOMER |
| CHECKED: J.S. | INSTALLATION DETAIL | |
| APPROVED: [Signature] | NO. RA3C LIGHTING KIT | |
| DATE MAY 19, 1962 | ROHN MANUFACTURING | DRAWING NO. |
| SCALE NONE | DIVISION OF [Logo] | C 620501-R9 |

| | | | |
|----|-----------------------|---------|----|
| R1 | ADD ERICKSON COUPLING | 6-19-60 | JB |
| R2 | ADDED A3C | 7-10-60 | JB |
| R3 | ADDED PART NOS. ETC. | 8-21-70 | RD |
| R4 | ADDED JB-#C NOTE | 8-17-76 | OK |

| | | |
|-----|----------|------|
| R2 | 11-9-70 | OK |
| R3 | 4-11-67 | A.S. |
| R4 | 11-13-62 | L.H. |
| NO. | REVISION | |

RA3C LIGHTING KIT

301' to 450' w/conduit
120 volt AC


| <u>Qty.</u> | <u>Part Number</u> | <u>Description</u> |
|--------------|--------------------|--|
| 4 | OB1 | Single obstruction lights |
| 4 | JB4TC | Junction boxes |
| 3 | JB4C | Junction boxes |
| 1 | 2532 | Water tight connector |
| 1 | 520028 | Short elbow 3/4" |
| 2 | CB1 | Conduit breathers |
| 6 | 520006 | Erickson couplings 3/4" |
| 2 | 520013 | Plastic pipe plugs 3/4" |
| 38 | 520002 | Conduit lock nuts 3/4" |
| 1 | WR100 | Can stainless steel wraplock (1/2" x 100') |
| 1 | 520023 | Can joint compound |
| 20' | 530021 | #14 TW wire (red) |
| 20' | 530023 | #14 TW wire (white) |
| 2 | 520007 | Conduit nipples 3/4" x 4" |
| 4 | 530002 | Conduit nipples 3/4" x 4" |
| 4 | * | Conduit nipples 3/4" x * |
| 1 | OBLITECAT | Obstruction lighting catalog |
| - | 530014 | #10 TW wire (red) (2/3 tower height plus 15') |
| 1 | A3RC | Flasher box w/flasher mechanism and remote photocell |
| 2 | KH90 | Saddle clamps |
| 4 | 210013G | Galvanized bolts 3/8" x 4" |
| 4 | 230005 | Heavy nuts 3/8" |
| 4 | 230007 | Pal nuts 3/8" |
| 4 | 250006 | Flat stainless steel washers 3/8" |
| 1 | 520036 | Nipple 1/2" x 4" |
| 1 | 520012 | Reducer 3/4" x 1/2" |
| 1 | 520040 | Elbow 1/2" |
| 3 | 520031 | Conduit lock nuts 1/2" |
| 1 | 520002 | Conduit lock nut 3/4" |
| 1 | * | Conduit nipple 3/4" x * |
| 1 | B1 | Beacon w/filters |
| 4 | B620W | Beacon bulbs (120 volt) |
| 8 | OB116W | Obstruction light bulbs (120 volt) |
| - | 530009 | #8 TW wire (black) (tower height plus 15') |
| - | 530011 | #8 TW wire (white) (tower height plus 15') |
| - | 520001 | Rigid galvanized conduit 3/4" (tower height) |

*Determined by face width.


Parts list may vary for self-supporting tower.

See Drawing No. C-620504-R6 for installation data.


PROPER ANCHOR INSTALLATIONS



SERVING



10" I BEAM STUB ANCHOR
WITH MICROPRESS
SLEEVES AND SAFETY
WIRE




SAFETY WIRE AND
GROUNDING

W. Moratti

BASIC LAYOUT - WALLS AND DOORS
FOR WRIU TRANSMITTER BLDG

NEW WALLS MUST CONFORM
TO NORMAL (HOUSE)
CONSTRUCTION STANDARDS -
10. SHOULD BE THERMALLY
INSULATED TO R-11 AND
SECURE AGAINST EASY
BREAK-IN.



WRIU TRANSMITTER BLDG
SCALE: NONE
4/29/81
KMT

TO ACHIEVE MAXIMUM COVERAGE WITH THE END-SLEEVE, THE APPLICATION SHOULD BE CONDUCTED IN THE FOLLOWING MANNER:

(BE SURE TO SELECT PROPER SIZE END-SLEEVE)



1
PLACE THE SLOT SIDE OF THE END-SLEEVE OVER THE LONG LEG OF THE DEAD-END.




2
DRIVE THE SLEEVE DOWNWARD UNTIL THE RODS OF SHORT LEG ARE COMPLETELY COVERED.





3
THE ENDS OF THE LONG LEG SHOULD BE EVEN WITH, OR MAY EXTEND ABOVE, THE TOP EDGE OF THE SLEEVE.

| | | | | | | | |
|--|--------------|----------------------|--------------------|---|------|--------------|-----------------------------|
| NO. R1 | | REVISIONS | | DATE 7-6-76 | | BY DM | |
| ROHN | | | | | | | |
| TITLE APPLICATION PROCEDURE FOR BIG-GRIP END SLEEVE | | | | | | | |
| THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT. | | | | | | FILE NO. | |
| SCALE NONE | MATERIAL | FINISH | HT | UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE GIVEN IN INCHES | | | |
| DATE 6-9-70 | BY DM | CHECKED BY DM | DATE 6-9-70 | SEC. | PAGE | SHEET | DWG. NO. B-700607 R1 |

PRINTED IN U.S.A.





NOTE :
 REMOVE ALL SHARP BENDS FROM COPPER WIRE




ANCHOR GROUNDING KITS


| REVISIONS | | | |
|---|-------------|----------|----------|
| NO. | DESCRIPTION | DATE | BY |
| ROHN MANUFACTURING | | | |
| TOWER GROUNDING METHODS | | | |
| THIS DRAWING IS THE PROPERTY OF ROHN. IF IT IS NOT TO BE REPRODUCED, COPIED, OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT. | | | |
| DATE | BY | CHKD BY | APP'D BY |
| NONE | VER | VER | VER |
| 11-20-73 | 11-20-73 | 11-20-73 | 11-20-73 |
| 11-27-73 | 11-27-73 | 11-27-73 | 11-27-73 |
| 12-17-73 | 12-17-73 | 12-17-73 | 12-17-73 |
| DWG NO. C-731105 | | | 2 |



TYPES-GAR-25 & GAC-25



TYPES-GAC-75,100,34,56 & 57



TYPES-GAC-88 & 59

ANCHOR ROD DETAILS



- 8) SEE DRAWING NO. C-730323 FOR ANCHOR ROD FAB. DETAILS
- 7) USE EQUALIZER PLATES EP-57 WITH 1/16" SLOT FOR GAC-100 SERIES ANCHORS
- 6) USE EQUALIZER PLATES EP-56 WITH 1/8" SLOT FOR GAC-75 SERIES ANCHORS
- 5) TYPE-EJ EQUALIZER PLATES ARE USED WITH EYE B JAW TURNBUCKLES
- 4) TYPE-EE EQUALIZER PLATES ARE SUPPLIED IN PAIRS FOR EYE B EYE TURNBUCKLES
- 3) PART NO. SUFFIXES -1,3,5,33 & 55 DENOTES -1,3 OR 5 HOLES IN PLATES
- 2) TYPE GAC-25 RODS ARE SUPPLIED WITH TYPE 2834-EE EQUALIZER PLATES
- 1) SEE DRAWING NO. C-660416-B FOR EQUALIZER PLATE DETAILS.

ANCHOR ROD DATA

| PART NUMBER | EQUALIZER PLATE TYPE | DIMENSIONS IN INCHES | | | | | | WEIGHT-LBS. | LOAD CAPACITY-LBS. |
|-------------|----------------------|----------------------|-------|--------|-------|-------|-----|-------------|--------------------|
| | | L | A | B | C | D | T | | |
| GAR-25 | EYE | 64 | 3/8 | 4 | 1 1/2 | 3/8 | — | 8 | 5,500 |
| GAC-25-3 | EE | 64 | 2 | 4 | 1 1/2 | 3/8 | 3/8 | 12 | 5,500 |
| GAC-25-5 | EE | 64 | 2 | 4 | 1 1/2 | 3/8 | 3/8 | 13 | 5,500 |
| GAC-75-1 | EJ | 120 | 1 1/8 | 12 | 3 | 3/4 | 1/2 | 25 | 13,250 |
| GAC-75-3 | EJ | 120 | 2 1/2 | 12 | 3 | 3/4 | 1/2 | 30 | 13,250 |
| GAC-75-5 | EJ | 120 | 2 1/2 | 12 | 3 | 3/4 | 1/2 | 35 | 13,250 |
| GAC-100-1 | EJ | 120 | 1 3/8 | 12 | 4 | 1 1/8 | 3/4 | 55 | 23,550 |
| GAC-100-3 | EJ | 120 | 3 | 12 | 4 | 1 1/8 | 3/4 | 65 | 23,550 |
| GAC-100-5 | EJ | 120 | 3 | 12 | 4 | 1 1/8 | 3/4 | 75 | 23,550 |
| GAC-34-33 | EJ | 84 | 2 | 12 | 2 1/2 | 3/4 | 3/8 | 20 | 13,250 |
| GAC-56-33 | EJ | 120 | 2 1/2 | 12 | 3 | 1 1/4 | 1/2 | 60 | 36,800 |
| GAC-57-33 | EJ | 168 | 3 | 12 | 4 | 1 1/4 | 3/4 | 115 | 48,600 |
| GAC-58-33 | EJ | 192 | 4 | 12 | 6 | 1 1/4 | 1 | 200 | 73,600 |
| GAC-59-33 | EJ | 240 | 4 | 18 (6) | 6 | 1 1/4 | 1 | 300 | 97,300 |
| GAC-34-55 | EJ | 84 | 2 | 12 | 2 1/2 | 3/4 | 3/8 | 25 | 13,250 |
| GAC-56-55 | EJ | 120 | 2 1/2 | 12 | 3 | 1 1/4 | 1/2 | 65 | 36,800 |
| GAC-57-55 | EJ | 168 | 3 | 12 | 4 | 1 1/4 | 3/4 | 125 | 48,600 |
| GAC-58-55 | EJ | 192 | 4 | 12 | 6 | 1 1/4 | 1 | 220 | 73,600 |
| GAC-59-55 | EJ | 240 | 4 | 18 (6) | 6 | 1 1/4 | 1 | 310 | 97,300 |

SEE NOTE B
SEE NOTE C

| | | | |
|---|-------------|------|-------|
| REVISED "ST ROD DIM. & CAPACITY" | 8-11-71 | TS | |
| DELETE "60 ROD, REVISE CAP #23,800" | 1-15-78 | WOK | |
| NO. | DESCRIPTION | DATE | BY |
| ROHN MANUFACTURING | | | |
| ANCHOR ROD SCHEDULE | | | |
| THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED COPIED, OR LOANED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT. | | | |
| DATE | BY | CHKD | APP'D |
| 1-22-73 | DM | | |
| 1-25-73 | | | |
| 3-28-73 | | | |
| C-660415 R. | | | |



NOTE: DUE TO VARIABLES INVOLVED IN ROOF AND OTHER INSTALLATIONS, IT SHALL BE THE CUSTOMER'S OR INSTALLER'S RESPONSIBILITY TO PROVIDE STRUCTURALLY ADEQUATE SUPPORTS FOR PIER & ANCHOR CONNECTIONS. IT MAY ALSO BE NECESSARY FOR THE CUSTOMER OR INSTALLER TO SECURE THE SERVICE OF A LOCAL ENGINEER TO DETERMINE THAT INSTALLATION COMPLIES WITH LOCAL BUILDING CODES.

- GENERAL NOTES
- * * 1. ANCHOR DESIGN ASSUMES E.I.R. NORMAL SOIL.
 - 2. CONCRETE, 3,000 PSI MINIMUM ULTIMATE STRENGTH.
 - 3. ASTM A-615 GRADE 40 DEFORMED REBARS.
 - 4. MINIMUM CONCRETE COVER ON ALL REBARS IS 2".
 - 5. MINIMUM 1/2" DIAMETER REINFORCING BARS IN ALL ANCHORS WITH MAXIMUM SPACING OF 12" EXCEPT NO. 10 BLOCK MAXIMUM SPACING OF 6".
 - 6. ALL FORMS MUST BE REMOVED FROM CONCRETE BEFORE PLACING COMPACTED BACKFILL.

CONCRETE ANCHOR DATA

| DEPTH, D (FT.) | ROD NO. | BLOCK NO. | ANCHOR DIMENSIONS (FT.) | | | WEIGHT (CONCRETE) (LBS.) | CONCRETE (CU. YDS.) | UPLIFT * CAPACITY (LBS.) | LATERAL CAPACITY (LBS.) |
|----------------|---------|-----------|-------------------------|-----|-----|--------------------------|---------------------|--------------------------|-------------------------|
| | | | A | B | C | | | | |
| 3 | GAC-25 | 3a | 1.5 | 1.5 | 1 | 310 | .08 | 900 | 1,500 |
| | | 3b | 2 | 2 | 1 | 560 | .15 | 1,320 | 2,000 |
| | | 3c | 2.5 | 2.5 | 1 | 870 | .23 | 1,810 | 2,500 |
| | | 3d | 3 | 3 | 1 | 1,260 | .33 | 2,535 | 3,000 |
| | | 3e | 3 | 4 | 1 | 1,680 | .44 | 3,020 | 4,000 |
| 4 | GAC-34 | 4a | 3 | 3 | 1.5 | 1,890 | .50 | 3,490 | 5,850 |
| | | 4b | 3 | 4 | 1.5 | 2,520 | .67 | 4,360 | 7,800 |
| | | 4c | 3 | 5 | 1.5 | 3,150 | .84 | 4,985 | 9,750 |
| | | 4d | 3 | 6 | 1.5 | 3,780 | 1.00 | 6,090 | 11,700 |
| | | 4e | 4 | 6 | 1.5 | 5,050 | 1.33 | 7,660 | 11,700 |
| 6 | GAC-56 | 6a | 3 | 4 | 1.5 | 2,520 | .67 | 10,035 | 12,600 |
| | | 6b | 3 | 5 | 1.5 | 3,150 | .84 | 11,600 | 15,150 |
| | | 6c | 3 | 6 | 1.5 | 3,780 | 1.00 | 13,150 | 18,900 |
| | | 6d | 4 | 6 | 1.5 | 5,050 | 1.33 | 15,850 | 18,900 |
| | | 6e | 3 | 5 | 1.5 | 3,150 | .84 | 22,150 | 21,750 |
| 8 | GAC-57 | 8a | 3 | 6 | 1.5 | 3,780 | 1.00 | 24,700 | 26,100 |
| | | 8b | 4 | 6 | 1.5 | 5,050 | 1.33 | 28,500 | 26,100 |
| | | 8c | 6 | 6 | 2.0 | 10,800 | 2.67 | 33,350 | 33,300 |
| | | 8d | 3 | 6 | 2.0 | 5,040 | 1.33 | 37,450 | 43,200 |
| | | 8e | 4 | 6 | 2.0 | 6,720 | 1.78 | 42,700 | 43,200 |
| 10 | GAC-58 | 10a | 4 | 7 | 2.0 | 7,840 | 2.07 | 46,800 | 50,400 |
| | | 10b | 5 | 7 | 2.0 | 9,800 | 2.59 | 52,350 | 50,400 |
| | | 10c | 4 | 9 | 2.0 | 12,600 | 3.33 | 61,700 | 63,800 |
| | | 10d | 5 | 9 | 2.0 | | | | |
| | | 10e | 5 | 9 | 2.0 | | | | |

* INCLUDES SAFETY FACTOR OF 2

* * NORMAL SOIL IS A COHESIVE TYPE SOIL WITH A HORIZONTAL BEARING CAPACITY OF 400 POUNDS PER SQUARE FOOT PER LINEAL FOOT OF DEPTH. ROCK, NON-COHESIVE SOILS, OR SATURATED OR SUBMERGED SOILS ARE NOT TO BE CONSIDERED AS NORMAL.



ROHN MANUFACTURING
DIVISION OF **GRABER**

TITLE: **STANDARD CONCRETE ANCHORS**

THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT.


DATE: 4-73
DWG. NO.: C-620643 R4

| NO. | DESCRIPTION | DATE | BY |
|-----|--------------------------------------|---------|-----|
| 1 | REVISED DESIGN NOTE 1 | 12-7-71 | JER |
| 2 | REVISED DESIGN NOTE 1, & TITLE BLOCK | 4/9/73 | GLS |
| 3 | REVISED DESIGN NOTE 1, & TITLE BLOCK | 4/9/73 | GLS |



| CONCRETE BASE SCHEDULE | | | | | | | | | | | |
|------------------------|------------------------|------------|-----|-----|-----|-----|-----|------------------|--------------------|-------------------------------|-----------------------------|
| CB NO. | TOWER BASE REACTION | DIMENSIONS | | | | | | BEARING PLATE | CONC. (CU. YDS) | VERTICAL BARS (NO. & SIZE) | HORIZ. BARS (NO. & SIZE) |
| | | A | B | C | D | E | F | | | | |
| 1 | 14000 | 2'0 | 2'0 | 0 | 4'0 | 0 | 0 | BP 6 | .70 | 4-NO.6 | NONE* |
| 2 | 22000 | 2'6 | 2'6 | 0 | 4'0 | 0 | 0 | BP 6 | 1.00 | 4-NO.6 | NONE* |
| 3 | 32000 | 3'0 | 3'0 | 0 | 4'0 | 0 | 0 | BP 6 | 1.50 | 4-NO.6 | NONE* |
| 4 | 44000 | 3'6 | 3'6 | 0 | 4'0 | 0 | 0 | BP 6 | 2.10 | 4-NO.6 | NONE* |
| 5 | 58000 | 2'0 | 4'0 | 1'0 | 4'0 | 3'3 | 1'3 | BP 6 | 1.22 | 4-NO.6 | 6-NO.4 |
| 6 | 74000 | 2'0 | 4'6 | 1'3 | 4'0 | 3'3 | 1'3 | BP 6 | 1.42 | 4-NO.6 | 6-NO.5 |
| 7 | 90000 | 2'0 | 5'0 | 1'6 | 4'6 | 3'9 | 1'3 | BP 10 | 1.70 | 8-NO.6 | 6-NO.5 |
| 8 | 109000 | 2'0 | 5'6 | 1'9 | 4'6 | 3'9 | 1'3 | BP 10 | 2.00 | 8-NO.6 | 6-NO.5 |
| 9 | 130000 | 2'0 | 6'0 | 2'0 | 4'6 | 3'6 | 1'6 | BP 10 | 2.50 | 8-NO.6 | 7-NO.5 |
| 10 | 150000 | 2'0 | 6'6 | 2'3 | 4'6 | 3'6 | 1'6 | BP 10 | 2.90 | 8-NO.6 | 8-NO.5 |
| 11 | 173000 | 2'6 | 7'0 | 2'3 | 5'0 | 3'9 | 1'9 | BP 15 | 4.00 | 8-NO.7 | 8-NO.6 |
| 12 | 198000 | 2'6 | 7'6 | 2'6 | 5'0 | 3'9 | 1'9 | BP 15 | 4.50 | 8-NO.7 | 8-NO.6 |
| 13 | 224000 | 2'6 | 8'0 | 2'9 | 5'0 | 3'9 | 1'9 | BP 15 | 5.00 | 8-NO.7 | 9-NO.6 |
| 14 | 251000 | 3'0 | 8'6 | 2'9 | 5'0 | 3'6 | 2'0 | BP 15 | 6.50 | 12-NO.7 | 9-NO.7 |
| 15 | 279000 | 3'0 | 9'0 | 3'0 | 5'0 | 3'6 | 2'0 | BP 15 | 7.20 | 12-NO.7 | 10-NO.7 |


NOTE: DUE TO VARIABLES INVOLVED IN ROOF AND OTHER INSTALLATIONS, IT SHALL BE THE CUSTOMER'S OR INSTALLER'S RESPONSIBILITY TO PROVIDE STRUCTURALLY ADEQUATE SUPPORTS FOR PIER & ANCHOR CONNECTIONS. IT MAY ALSO BE NECESSARY FOR THE CUSTOMER OR INSTALLER TO SECURE THE SERVICE OF A LOCAL ENGINEER TO DETERMINE THAT INSTALLATION COMPLIES WITH LOCAL BUILDING CODES.



CB1 THRU CB6



CB7 THRU CB13



CB14 & CB 15

GENERAL NOTES:

1. BASE PIER DESIGNED FOR AN ALLOWABLE NET SOIL PRESSURE OF 4000 PSF.
2. CONCRETE - 3000 PSI MIN. ULT. STRENGTH AT 28 DAYS.
3. REINFORCING STEEL - ASTM A-615 GRADE 40 DEFORMED BARS.
4. MIN. COVER ON ALL REINFORCING STEEL IS 3".
5. ALL FORMS MUST BE REMOVED FROM CONCRETE BEFORE PLACING COMPACTED BACKFILL.
6. VERTICAL REINFORCING STEEL MAY BE PLACED WITH AN OPTIONAL STANDARD ACI 90° BEND AT BOTTOM.
7. FOUNDATION DESIGN PER E. I. A. STANDARDS.
8. BEARING PLATE PROVIDED ONLY ON TOWERS WITH TAPERED BASES.
9. HORIZ. BARS IN CHART REFER ONLY TO THE BARS IN THE FOUNDATION PAD.

TIE BAR DETAILS

| | | | |
|-----|--------------------------------|---------|----|
| RE | ADDED NOTE | 7-6-76 | DA |
| RE | RE-DRAWN - SUPERSEDES C610621D | 2-26-75 | DA |
| NO. | DESCRIPTION | DATE | BY |

ROHN MANUFACTURING

CONCRETE BASE SCHEDULE

C 610621 R3


PRINTED IN U.S.A.

| | | | |
|----|---------------------------------|---------|-----|
| RS | ADDED GENERAL NOTE #3 | 1-21-80 | VND |
| C | REMOVED RS-220-3 FROM COLUMN 13 | 3/27/77 | GIS |
| C | DELETE SIZE PIER PIN. | 7/23/76 | GES |

C-661004


MOUNTING BRACKET TYPE SAB
WITH SUPPORT TUBE

SIDE ARM WITH SUPPORT TUBE TYPE SA
AVAILABLE WITH SUPPORT TUBE
AT 2 FT., 4 FT. OR 6 FT. FROM
TOWER.




STANDARD AG-2
TOP SECTION
SHOWN

TOP MOUNTING



SIDE MOUNTING
(AT ANY LEVEL)



TOP MOUNTING
(WITH BEACON)

| NO. | REVISION | BY | DATE | DRAWN CK. |
|-----|-----------|----|---------------|--------------------|
| 1 | PREP. AWL | SM | 12-1-58 | CHECKED |
| | | | | APPROVED <i>JH</i> |
| | | | DATE 10-12-58 | |
| | | | SCALE NONE | |

| | |
|--|-------------------------|
| ANTENNA MOUNTING DETAILS | |
| ROHN MANUFACTURING PEORIA, ILLINOIS | DRAWING NO. C-661004 |

THIS DRAWING SUPERSEDES DRAWING NO. C-661004 AND C-661005

UNIVERSITY OF RHODE ISLAND RADIO REPLACEMENT 875 PLAINS ROAD TOWN OF SOUTH KINGSTON WASHINGTON COUNTY, RI 02892



CONSTRUCTION DRAWINGS

PROJECT CONTACTS

| NAME | COMPANY | NUMBER |
|---------------------------|--|----------------|
| APPLICANT KYLE COLEMAN | UNIVERSITY OF RHODE ISLAND OFFICE OF CAPITAL BUILDINGS 60 TOTTIELL ROAD - SHERMAN BUILDING KINGSTON, RI 02881 | (401) 500-1064 |
| A/E EDWARD JAV.CELI | TECTONIC ENGINEERING CONSULTANTS INC. 1279 ROUTE 300 NEWBURGH, NY 12550 | (845) 567-6656 |

PROJECT INFORMATION

| | |
|-----------------|---|
| SCOPE OF WORK: | EXISTING EQUIPMENT SHELTER AND ASSOCIATED EQUIPMENT ALONG WITH THE FOUNDATION SHALL BE DEMOLISHED. A PROPOSED 400' GUYED TOWER, PROPOSED SHELTER & GENERATOR ON A PROPOSED CONCRETE FOUNDATION ARE TO BE INSTALLED WITHIN THE NEW FENCED-IN COMPOUND. |
| SITE ADDRESS: | 875 PLAINS ROAD TOWN OF SOUTH KINGSTON WASHINGTON COUNTY, RI 02892 |
| PROPERTY OWNER: | UNIVERSITY OF RHODE ISLAND |
| APPLICANT: | UNIVERSITY OF RHODE ISLAND |
| LATITUDE: | 41° 29' 51.64" N (NAD 83) |
| LONGITUDE: | 71° 31' 41.93" W (NAD 83) |
| ELEVATION: | 1812' ± AMSL (NAD 83) |
| JURISDICTION: | TOWN OF SOUTH KINGSTON |
| PARCEL ID: | MAP 15-2, LOT 1 |



DRAWING INDEX

| SHEET NO | DWG NO | DRAWING TITLE | REV | DATE |
|----------|--------|---|-----|------------|
| 1 OF 16 | T001 | TITLE SHEET | 3 | 8/26/2024 |
| 2 OF 16 | T002 | GENERAL/SITR NOTES, TESTING & INSPECTIONS | 3 | 8/26/2024 |
| 3 OF 16 | T003 | FOUNDATION NOTES, LEGEND & ABBREVIATIONS | 3 | 8/26/2024 |
| 4 OF 16 | C100 | OVERALL SITE PLAN | 3 | 8/26/2024 |
| 5 OF 16 | C101 | SITE DEMOLITION PLAN & ENLARGED SITE PLAN | 3 | 8/26/2024 |
| 6 OF 16 | C200 | TOWER ELEVATION & OWN ANTENNA PLANS | 3 | 8/26/2024 |
| 7 OF 16 | C500 | TYPICAL DETAILS | 3 | 8/26/2024 |
| 8 OF 16 | C501 | SIGNAGE ELEVATION & DETAILS | 3 | 8/26/2024 |
| 9 OF 16 | C502 | STRUCTURAL PLANS, SECTIONS, & DETAILS | 3 | 8/26/2024 |
| 10 OF 16 | E100 | ROUTING PLAN | 2 | 6/18/2024 |
| 11 OF 16 | E101 | RISER DIAGRAM & NOTES | 2 | 6/18/2024 |
| 12 OF 16 | E102 | PRELIMINARY WIRING SCHEMATICS | 2 | 6/18/2024 |
| 13 OF 16 | G100 | GROUNDING PLAN & NOTES | 2 | 6/18/2024 |
| 14 OF 16 | G500 | GROUNDING DETAILS & NOTES | 2 | 6/18/2024 |
| 15 OF 16 | G501 | GROUNDING DETAILS | 2 | 6/18/2024 |
| 16 OF 16 | G502 | GROUNDING DETAILS | 2 | 6/18/2024 |
| 1 OF 2 | SV-100 | SURVEY BY OTHERS EXISTING SITE OVERVIEW PLAN | 0 | 12/12/2023 |
| 2 OF 2 | SV-101 | EXISTING CONDITIONS AND TOPOGRAPHY PLAN | 0 | 8/9/2023 |

SCOPE OF THIS DRAWING IS LIMITED TO THE DESIGN AND CONSTRUCTION OF THE TOWER AND ASSOCIATED EQUIPMENT. THE CLIENT IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE TOWN OF SOUTH KINGSTON AND THE STATE OF RHODE ISLAND. THE CLIENT SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE TOWN OF SOUTH KINGSTON AND THE STATE OF RHODE ISLAND. PLANS ARE NOT TO BE SCALED.



THE
UNIVERSITY
OF RHODE ISLAND

| Rev | Date | Description | By | Checked | Approved |
|-----|-----------|-------------------|----|---------|----------|
| 1 | 8/26/2024 | ISSUED FOR BID | | | |
| 2 | 8/26/2024 | ISSUED FOR PERMIT | | | |
| 3 | 8/26/2024 | ISSUED FOR PERMIT | | | |
| 4 | 8/26/2024 | ISSUED FOR PERMIT | | | |

Tectonic
TECTONIC ENGINEERING CONSULTANTS INC.
1279 ROUTE 300
NEWBURGH, NY 12550
www.tectonic-engineering.com



| TITLE SHEET | | | |
|--|-----------|-------------|------|
| PROPOSED GUYED TOWER 875 PLAINS ROAD TOWN OF SOUTH KINGSTON WASHINGTON COUNTY, RI 02892 | | | |
| Scale | Sheet No. | Drawing No. | Rev. |
| AS SHOWN | 12117.01 | T001 | 3 |

SPECIAL INSPECTIONS REQUIRED

1. INSPECTION REQUIRED - NO. 1-10-1
2. INSPECTION REQUIRED - NO. 1-10-2
3. INSPECTION REQUIRED - NO. 1-10-3
4. INSPECTION REQUIRED - NO. 1-10-4
5. INSPECTION REQUIRED - NO. 1-10-5
6. INSPECTION REQUIRED - NO. 1-10-6
7. INSPECTION REQUIRED - NO. 1-10-7
8. INSPECTION REQUIRED - NO. 1-10-8
9. INSPECTION REQUIRED - NO. 1-10-9
10. INSPECTION REQUIRED - NO. 1-10-10

REQUIRED SUBMITTALS

1. CONTRACT DOCUMENTS
2. PERMITS
3. FOUNDATION DESIGN DATA
4. DELEGATED DESIGN
5. NFPA NOTES

TESTING PROCEDURES REQUIRED

1. TESTING PROCEDURES REQUIRED FOR CONCRETE
2. TESTING PROCEDURES REQUIRED FOR STEEL
3. TESTING PROCEDURES REQUIRED FOR WELDS
4. TESTING PROCEDURES REQUIRED FOR SOILS
5. TESTING PROCEDURES REQUIRED FOR FOUNDATIONS

DESIGN CRITERIA

| | |
|-------------|--------------------------------|
| LOCATION | TOWN OF PROVIDENCE |
| DESIGN CODE | ASCE 7-16 & IBC 2018 |
| WIND SPEED | 110 MPH (ASCE 7-16) |
| SEISMIC | ASCE 7-16 (ASCE 7-16) |
| SOIL TYPE | CLAY (ASCE 7-16) |
| FOUNDATION | CONCRETE |
| DESIGNER | TECTONIC |
| DATE | 12/11/2023 |
| SCALE | AS SHOWN |
| PROJECT NO. | 12117.01 |
| CLIENT | THE UNIVERSITY OF RHODE ISLAND |

FOUNDATION DESIGN DATA

| | |
|-----------------------|----------|
| FOUNDATION TYPE | CONCRETE |
| FOUNDATION SIZE | AS SHOWN |
| FOUNDATION DEPTH | AS SHOWN |
| FOUNDATION MATERIAL | CONCRETE |
| FOUNDATION FINISH | AS SHOWN |
| FOUNDATION TOLERANCES | AS SHOWN |

DELEGATED DESIGN

THE DESIGNER HAS REVIEWED THE FOUNDATION DESIGN DATA AND HAS DETERMINED THAT THE FOUNDATION DESIGN DATA IS COMPLETE AND ACCURATE AND THAT THE FOUNDATION DESIGN DATA IS IN ACCORDANCE WITH THE REQUIREMENTS OF THE DESIGN CRITERIA.

NFPA NOTES

THE FOUNDATION DESIGN DATA IS IN ACCORDANCE WITH THE REQUIREMENTS OF THE NFPA 704 CODE.


FOUNDATION NOTES

1. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE DESIGN CRITERIA AND THE FOUNDATION DESIGN DATA.
2. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE NFPA 704 CODE.
3. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE IBC 2018 CODE.
4. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
5. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
6. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
7. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
8. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
9. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
10. FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.

STRUCTURAL STEEL NOTES

1. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE DESIGN CRITERIA AND THE STRUCTURAL STEEL DESIGN DATA.
2. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE NFPA 704 CODE.
3. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE IBC 2018 CODE.
4. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
5. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
6. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
7. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
8. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
9. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.
10. STRUCTURAL STEEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ASCE 7-16 CODE.

DATE OF THIS DESIGN: 12/11/2023
 THE UNIVERSITY OF RHODE ISLAND
 600 SOUTH MAIN STREET
 PROVIDENCE, RHODE ISLAND 02903
 TEL: 401-874-5000
 FAX: 401-874-5001
 WWW: UR.EDU




THE UNIVERSITY OF RHODE ISLAND

| No. | Date | Revised | By | Checked | Approved |
|-----|------------|--------------------|----|---------|----------|
| 1 | 12/11/2023 | ISSUED FOR PERMITS | TJ | MS | MS |
| 2 | 12/11/2023 | ISSUED FOR PERMIT | TJ | MS | MS |
| 3 | 12/11/2023 | ISSUED FOR PERMIT | TJ | MS | MS |

Tectonic
 STRUCTURAL ENGINEERING
 1000 WEST MAIN STREET
 PROVIDENCE, RHODE ISLAND 02903
 TEL: 401-874-5000
 FAX: 401-874-5001
 WWW: TECTONIC-RI.COM

| NO. | DATE | REVISION | BY | CHECKED | APPROVED |
|-----|------------|--------------------|----|---------|----------|
| 1 | 12/11/2023 | ISSUED FOR PERMITS | TJ | MS | MS |
| 2 | 12/11/2023 | ISSUED FOR PERMIT | TJ | MS | MS |
| 3 | 12/11/2023 | ISSUED FOR PERMIT | TJ | MS | MS |



SCALE OF THIS DRAWING SHALL BE THE SAME AS THE SCALE OF THE PLAN OF THE SITE OF THE UNIVERSITY OF RHODE ISLAND. THE SCALE OF THIS DRAWING SHALL BE THE SAME AS THE SCALE OF THE PLAN OF THE SITE OF THE UNIVERSITY OF RHODE ISLAND. THE SCALE OF THIS DRAWING SHALL BE THE SAME AS THE SCALE OF THE PLAN OF THE SITE OF THE UNIVERSITY OF RHODE ISLAND.




THE UNIVERSITY OF RHODE ISLAND

| REV | DATE | DESCRIPTION | BY | CHKD |
|-----|------------|-------------------|----|------|
| 1 | 11/17/2010 | ISSUED FOR BID | | |
| 2 | 11/17/2010 | ISSUED FOR PERMIT | | |
| 3 | 11/17/2010 | ISSUED FOR PERMIT | | |
| 4 | 11/17/2010 | ISSUED FOR PERMIT | | |

Tectonic
 Tectonic Engineering & Construction, Inc.
 1777 North Main Street
 North Kingstown, RI 02881
 Phone: (401) 887-3000
 Fax: (401) 887-3000
 www.tectonic-engineering.com




| SITE DEMOLITION PLAN & ENLARGED SITE PLAN | | | |
|--|---------|-----------------|-------------|
| PROPOSED GUYED TOWER 875 PLAINS ROAD TOWN OF SOUTH KINGSTON WASHINGTON COUNTY, RI 02892 | | | |
| DATE: 11/17/2010 | REV: 01 | SCALE: 1" = 20' | SHEET NO: 3 |
| PROJECT NO: 12117.01 | C101 | | |




NOTES
 1. STRUCTURAL INTEGRITY OF PROPOSED TOWER SHALL BE ASSESSED BY OTHERS.
 2. TOWER LIGHTING SHALL BE RED AND WHITE 'DUAL MODE' LIGHTING.

| PROPOSED ANTENNA/CABLE CONFIGURATION SCHEDULE | | | | | | |
|---|--------------|--------------------|--------------|----------------|----------------------|-----------------|
| HEIGHT FROM GROUND (FT) | ELEMENT TYPE | NUMBER OF ELEMENTS | ANTENNA TYPE | ANTENNA PIVOT | NUMBER OF FEED LINES | FEED LINE TYPE |
| 210'-0" | 210'-0" | 1 | FM ANTENNA | 4 80' - 80' 0" | 1 | 1-5/8" FEEDLINE |
| 210'-0" | 210'-0" | 1 | FM ANTENNA | 4 80' - 80' 0" | 1 | 1-5/8" FEEDLINE |
| 210'-0" | 210'-0" | 1 | FM ANTENNA | 4 80' - 80' 0" | 1 | 1-5/8" FEEDLINE |
| 210'-0" | 210'-0" | 1 | FM ANTENNA | 4 80' - 80' 0" | 1 | 1-5/8" FEEDLINE |
| 210'-0" | 210'-0" | 1 | FM ANTENNA | 4 80' - 80' 0" | 1 | 1-5/8" FEEDLINE |



① FIXED STATION RADIO SYSTEM @ 60'-0" LEVEL
 SCALE: N/A



② FM BAY ANTENNA PLAN (TYP)
 SCALE: N/A

③ TOWER ELEVATION
 SCALE: 3/8" = 1'-0"

NOTES:
 1. THIS DOCUMENT PROVIDES INFORMATION FOR THE DESIGN AND CONSTRUCTION OF THE TOWER AND ANTENNA SYSTEMS. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES.
 PLANS ARE NOT TO BE SCALED.




THE UNIVERSITY OF RHODE ISLAND


| REV | DATE | DESCRIPTION | BY | CHKD |
|-----|----------|-------------------|----|------|
| 1 | 12/15/20 | ISSUED FOR BID | | |
| 2 | 12/15/20 | ISSUED FOR PERMIT | | |
| 3 | 12/15/20 | ISSUED FOR PERMIT | | |
| 4 | 12/15/20 | ISSUED FOR PERMIT | | |

Tectonic
 Tectonic Engineering, Inc.
 1275 Route 1
 Narragansett, RI 02882

TOWER ELEVATION & OMNI ANTENNA PLANS
 PROPOSED GUYED TOWER
 975 PLAINS ROAD
 TOWN OF SOUTH KINGSTON
 WASHINGTON COUNTY, RI 02892
 DATE: 12/15/20
 SHEET NO: C200
 OF: 3



COPIES OF THIS DOCUMENT, IF NOT A PORTION OF THE PROJECT OR AN OFFICIAL RECORD, SHALL BE OF THE PROPERTY OF THE UNIVERSITY OF RHODE ISLAND. ANY REPRODUCTION OR TRANSMISSION OF THIS DOCUMENT WITHOUT THE WRITTEN PERMISSION OF THE UNIVERSITY OF RHODE ISLAND IS PROHIBITED. THE UNIVERSITY OF RHODE ISLAND IS NOT RESPONSIBLE FOR ANY DAMAGE TO PERSONS OR PROPERTY THAT MAY OCCUR AS A RESULT OF THE USE OF THIS DOCUMENT. PLANS ARE NOT TO BE SCALED.



| NO. | DATE | REVISION | BY | CHECKED |
|-----|----------|-------------------|----|---------|
| 1 | 5/1/2011 | ISSUED FOR BID | | |
| 2 | 5/1/2011 | ISSUED FOR PERMIT | | |
| 3 | 5/1/2011 | ISSUED FOR PERMIT | | |
| 4 | 5/1/2011 | ISSUED FOR PERMIT | | |


Tectonic
Engineering & Construction, Inc.
1276 Avenue B
Narragansett, RI 02882
Phone: (401) 881-8833
Fax: (401) 881-5211
www.tectoniceng.com

TYPICAL DETAILS


PROPOSED GUYED TOWER
875 PLAINS ROAD
TOWN OF SOUTH KINGSTON
WASHINGTON COUNTY, RI 02892

DATE: 5/1/2011
SCALE: 1/2" = 1'-0"

PROJECT NO: 12117-01
SHEET NO: C600
OF 3




1 SIGNAGE ELEVATION
SCALE: 1/8\"/>




2 FCC REGISTRATION SIGN
SCALE: 1/8\"/>

3 NO TRESPASSING SIGN
SCALE: 1/8\"/>


4 NOTICE-RFE SIGN
SCALE: 1/8\"/>





5 RF CAUTION SIGN
SCALE: 1/8\"/>



6 CAUTION-HARD HAT CONSTRUCTION AREA AND TRIPPING HAZARDS
SCALE: 1/8\"/>



7 CABLE LADDER DETAIL
SCALE: 1/8\"/>



8 ALARM REPORTING SYSTEM SAMPLE ELEVATION
SCALE: 1/8\"/>

NOTICE: THE DESIGNER'S RESPONSIBILITY IS LIMITED TO THE DESIGN OF THE SYSTEM AS SHOWN ON THESE PLANS. THE USER OF THESE PLANS SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION AND MAINTENANCE OF THE SYSTEM. THE USER SHALL BE RESPONSIBLE FOR THE PROPER OPERATION AND MAINTENANCE OF THE SYSTEM. THE USER SHALL BE RESPONSIBLE FOR THE PROPER OPERATION AND MAINTENANCE OF THE SYSTEM. PLANS ARE NOT TO BE SCALED.




THE UNIVERSITY OF RHODE ISLAND

| Rev | Date | Description | By | Checked | Approved |
|-----|---------|--------------------|----|---------|----------|
| 1 | 11/1/01 | ISSUED FOR BID | | | |
| 2 | 11/1/01 | REVISED FOR PERMIT | | | |
| 3 | 11/1/01 | REVISED FOR PERMIT | | | |
| 4 | 11/1/01 | REVISED FOR PERMIT | | | |

Tectonic
PROFESSIONAL ENGINEERING, ARCHITECTURAL SERVICES
Tectonic Engineering Consultants, Inc.
1175 North 20th Street
Providence, RI 02909
Phone: (401) 847-8822
Fax: (401) 847-8822
www.tectonicinc.com




| SIGNAGE ELEVATION & DETAILS | | | |
|--|-------------|-------------|-----------------|
| PROPOSED TOWER 870 PLAINS ROAD TOWN OF SOUTH KINGSTON WASHINGTON COUNTY, RI 02892 | | | |
| DATE: 12/11/01 | SCALE: C601 | SHEET NO: 3 | TOTAL SHEETS: 3 |




1. PRIOR TO CONSTRUCTION AND FABRICATION OF THE FOUNDATION SYSTEM CONTRACTOR SHALL COORDINATE THE FOUNDATION REQUIREMENTS WITH THE SHELTER MANUFACTURER. APPROVE FOUNDATION AND FOUNDATION REQUIREMENTS WITH THE SHELTER MANUFACTURER.

2. SHELTER CONTRACTOR TO PROVIDE FOUNDATION SYSTEM SHALL BE RESPONSIBLE FOR THE DESIGN OF THE FOUNDATION SYSTEM. CONTRACTOR SHALL PROVIDE A BASIS OF DESIGN TO THE SHELTER MANUFACTURER. CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN OF THE FOUNDATION SYSTEM. CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN OF THE FOUNDATION SYSTEM.


EQUIPMENT SHELTER FDN PLAN
SCALE: 1/4" = 1'-0"




TYP FDN WALL CORNER DETAIL
SCALE: 1/2" = 1'-0"




TYP CONDUIT SLEEVE DETAIL
SCALE: 1/2" = 1'-0"



CONC LANDING SECTION
SCALE: 1/2" = 1'-0"



TYPICAL SHELTER FOUNDATION SECTIONS
SCALE: 1/2" = 1'-0"



GENERATOR FDN SECTION
SCALE: 1/2" = 1'-0"

| DIMENSION | SIZE | MIN. L ₁ | MIN. L ₂ | MIN. L ₃ |
|-----------|------|---------------------|---------------------|---------------------|
| 1 | #4 | 12" | 12" | 12" |
| 2 | #5 | 18" | 18" | 18" |
| 3 | #6 | 24" | 24" | 24" |
| 4 | #7 | 30" | 30" | 30" |
| 5 | #8 | 36" | 36" | 36" |

- NOTES**
1. REINFORCEMENT SIZE AND SPACING FOR WALL SHALL BE AS SHOWN. CONTRACTOR SHALL VERIFY THE REINFORCEMENT SIZE AND SPACING FOR THE WALL IS CORRECTLY PROVIDED AND SHOWN ON PLAN IS CORRECTLY PROVIDED.
 2. A MINIMUM OF 3 REBAR TO CONCRETE SHALL BE IN REINFORCEMENT.
 3. ALL REBAR SHALL BE PROVIDED WITH BENDS. NO REBAR SHALL BE PROVIDED IN THE SHELTER CONTRACTOR'S FOUNDATION TO THE SHELTER MANUFACTURER'S REQUIREMENTS.
 4. FOUNDATION REQUIREMENTS OF SHELTER SHALL BE PROVIDED BY THE SHELTER MANUFACTURER AND CONTRACTOR SHALL VERIFY THE FOUNDATION SHALL BE AS SHOWN ON PLAN.
 5. FOUNDATION SHALL BE AS SHOWN ON PLAN.


UNIVERSITY OF RHODE ISLAND
THE UNIVERSITY OF RHODE ISLAND

| REV | DATE | DESCRIPTION | BY | CHKD |
|-----|----------|--------------------|----|------|
| 1 | 1/1/2024 | ISSUED FOR BID | | |
| 2 | 1/1/2024 | REVISED FOR PERMIT | | |
| 3 | 1/1/2024 | REVISED FOR PERMIT | | |
| 4 | 1/1/2024 | REVISED FOR PERMIT | | |

Tectonic
Engineering & Construction, Inc.
1378 SOUTH ST
WARRING, RI 02892

STRUCTURAL PLANS, SECTIONS, & DETAILS
PROPOSED GUYED TOWER
875 HILLS ROAD
TOWN OF SOUTH KINGSTON
WASHINGTON COUNTY, RI 02892

DATE: 12/11/2023
SCALE: C502



ROUTING PLAN
SCALE: 1/8" = 1'-0"

THIS PLAN IS THE PROPERTY OF THE UNIVERSITY OF RHODE ISLAND. IT IS TO BE USED ONLY FOR THE PROJECT AND NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. ANY UNAUTHORIZED REPRODUCTION OR TRANSMISSION IS STRICTLY PROHIBITED. THE UNIVERSITY OF RHODE ISLAND ACCEPTS NO LIABILITY FOR ANY DAMAGE OR LOSS OF PROFITS, BUSINESS, OR REPUTATION, OR FOR ANY SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING ATTORNEY'S FEES, ARISING FROM THE USE OF THIS PLAN. PLANS ARE NOT TO BE SCALED.



THE UNIVERSITY OF RHODE ISLAND

CEN TEK engineering
Contract & Solution
2025 444-1112
2025 444-1113
2025 444-1114


| Rev | Date | Description | By | Checked |
|-----|------------|-------------------|----------|----------|
| 1 | 11/15/2024 | ISSUED FOR RFP | J. Smith | M. Jones |
| 2 | 11/20/2024 | ISSUED FOR PERMIT | J. Smith | M. Jones |
| 3 | 11/25/2024 | ISSUED FOR REVIEW | J. Smith | M. Jones |

Tectonic
Professional Engineering Consultants, Inc.
1200 Main Street, Suite 200
Providence, RI 02903
Phone: (401) 841-8822
Fax: (401) 841-8823
www.tectonic-engineering.com



| ROUTING PLAN | | | |
|--|-----------|-------------|----------|
| PROPOSED GUYED TOWER 675 PLAINS ROAD TOWN OF SOUTH KINGSTON WASHINGTON COUNTY, RI 02892 | | | |
| Scale | Sheet No. | Sheet Total | Date |
| 1/8" = 1'-0" | E100 | 2 | 11/17/01 |

| KEY NOTE LEGEND | |
|----------------------------|---------------------------------------|
| ABBREVIATIONS | |
| 1. DWTN ELECTRICAL SERVICE | |
| NOTES | |
| 1. | SEE ELECTRICAL CODE BOOK |
| 2. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 3. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 4. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 5. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 6. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 7. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 8. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 9. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 10. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 11. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 12. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 13. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 14. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 15. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 16. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 17. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 18. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 19. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 20. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 21. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 22. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 23. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 24. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 25. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 26. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 27. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 28. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 29. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 30. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 31. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 32. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 33. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 34. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 35. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 36. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 37. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 38. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 39. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 40. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 41. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 42. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 43. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 44. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 45. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 46. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 47. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 48. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 49. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 50. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 51. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 52. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 53. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 54. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 55. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 56. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 57. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 58. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 59. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 60. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 61. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 62. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 63. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 64. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 65. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 66. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 67. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 68. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 69. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 70. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 71. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 72. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 73. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 74. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 75. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 76. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 77. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 78. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 79. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 80. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 81. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 82. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 83. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 84. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 85. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 86. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 87. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 88. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 89. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 90. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 91. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 92. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 93. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 94. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 95. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 96. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 97. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 98. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 99. | SEE ALL WIRING FOR PROTECTIVE DEVICES |
| 100. | SEE ALL WIRING FOR PROTECTIVE DEVICES |



NOTE: ALL WIRING SHALL BE IN ACCORDANCE WITH ALL ELECTRICAL CODES FOR UNLICENSED INSTALLATIONS.
RISER DIAGRAM
 SCALE: 1/8" = 1'-0"

THIS DOCUMENT IS THE PROPERTY OF THE UNIVERSITY OF RHODE ISLAND. IT IS LOANED TO YOU FOR YOUR USE ONLY. IT IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. ANY UNAUTHORIZED USE OF THIS DOCUMENT IS PROHIBITED. ALL RIGHTS RESERVED.



THE UNIVERSITY OF RHODE ISLAND

CENTEK Engineering
 General & Civil
 1078 BOSTON
 1078 BOSTON
 1078 BOSTON


| REV | DATE | DESCRIPTION | BY | CHKD |
|-----|----------|-------------------|----|------|
| 1 | 11/15/01 | ISSUED FOR BID | | |
| 2 | 11/15/01 | ISSUED FOR PERMIT | | |
| 3 | 11/15/01 | ISSUED FOR PERMIT | | |

| NO. | DATE | DESCRIPTION |
|-----|----------|-------------------|
| 1 | 11/15/01 | ISSUED FOR BID |
| 2 | 11/15/01 | ISSUED FOR PERMIT |
| 3 | 11/15/01 | ISSUED FOR PERMIT |

Tectonic
 Tectonic Engineering Solutions, Inc.
 1178 Route 300
 Northbury, VT 05703
 Phone: (802) 847-0010
 Fax: (802) 847-0011
 www.tectonic-engineering.com



| RISER DIAGRAM & NOTES | | | |
|--|----------|-------|--------------|
| PROPOSED GUYED TOWER 875 PLAINS ROAD TOWN OF SOUTH KINGSTON WASHINGTON COUNTY, RI 02892 | | | |
| DATE | 12/17/01 | SCALE | 1/8" = 1'-0" |
| PROJECT NO. | 12117.01 | DATE | 12/17/01 |
| BY | | CHKD | |
| DATE | | DATE | |



EXTERIOR GROUNDING PLAN
SCALE: 1" = 8'

INTERIOR GROUNDING PLAN (SHELTER)
SCALE: 1" = 10'

THIS PLAN IS FOR INFORMATION ONLY. IT IS NOT TO BE USED FOR CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS AND CONDITIONS ON THE JOB. THE ENGINEER'S RESPONSIBILITY IS LIMITED TO THE DESIGN OF THE ELECTRICAL SYSTEM SHOWN ON THIS PLAN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND FOR COMPLYING WITH ALL APPLICABLE CODES AND REGULATIONS. THIS PLAN IS NOT TO BE SCALED.



THE UNIVERSITY OF RHODE ISLAND

CENEX engineering
Contractors & Engineers
6028 141-2103
6028-141-2103
6028-141-2103

| Rev | Date | Revised | By | Checked | Approved |
|-----|----------|---------------------|----|---------|----------|
| 1 | 1/1/2020 | ISSUED FOR NO | | | |
| 2 | 1/1/2020 | ISSUED FOR PERMIT | | | |
| 3 | 1/1/2020 | ISSUED FOR AS-BUILT | | | |










Tectonic
Engineering & Construction Services
11111 Route 100
Northampton, MA 01060
Phone: (413) 541-1111
Fax: (413) 541-1111
www.tectoniceng.com




| GROUNDING PLANS & NOTES | | | |
|--|----------|-----------|------|
| PROPOSED GUYED TOWER 875 PLAINS ROAD TOWN OF SOUTH KINGSTON WASHINGTON COUNTY, RI 02882 | | | |
| Project No. | 12117.01 | Sheet No. | G100 |
| Scale | | Date | 2 |

GROUNDING NOTES

- THE ENTIRE ELECTRICAL INSTALLATION SHALL BE INSTALLED AS REQUIRED BY THE NEC (NFPA 70) AND ALL OTHER APPLICABLE CODES.
- ONLY ONE GROUNDING SYSTEM SHALL BE USED UNLESS OTHERWISE NOTED. ALL SYSTEMS OF THE SAME TYPE SHALL BE INSTALLED IN THE SAME MANNER AND SHALL BE IDENTIFICATION MARKED.
- ALL INTERCONNECTING ELECTRICAL SYSTEMS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.
- ALL GROUNDING CONNECTIONS SHALL BE IDENTIFICATION MARKED AND SHALL BE IDENTIFICATION MARKED.



SCALE: 1/8\"/>




CENTEK Engineering
General Contractor

| REV | DATE | DESCRIPTION | BY | CHKD |
|-----|----------|-------------------|----|------|
| 1 | 11/15/10 | ISSUED FOR BID | | |
| 2 | 11/15/10 | ISSUED FOR PERMIT | | |
| 3 | 11/15/10 | ISSUED FOR POWER | | |


Tectonic
Tectonic Engineering Corporation, Inc.
1775 Route 330
Northvale, NJ 07648

GROUNDING DETAILS & NOTES
PROPOSED GUINER TOWER
878 PLAINS ROAD
TOWNSHIP OF SOUTH KINGSTON
WASHINGTON COUNTY, RI 02892


DATE: 11/17/10
DRAWING NO: 6500
PAGE: 2




1 IPBB CONDUCTOR RING GROUND TAP
SCALE: 1/8"




2 CONDUIT BOND DETAILS
SCALE: 1/8"




3 CABLE RACK BRACKET FOR GROUND WIRE
SCALE: 1/8"




4 CABLE RACK BONDING AT CORNER
SCALE: 1/8"




5 CABLE RACK BONDING AT SPLICE
SCALE: 1/8"




6 EQUIPMENT GROUND TAP
SCALE: 1/8"




7 GROUNDING CONNECTION
SCALE: 1/8"




8 GROUND BAR WALL INSTALLATION
SCALE: 1/8"



9 GROUND BAR TOWER INSTALLATION DETAIL
SCALE: 1/8"




10 EQUIPMENT GROUNDING ELEVATION
SCALE: 1/8"



11 EXOTHERMIC (CADMELD) DETAILS
SCALE: 1/8"

NOTE: ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED.
ALL DIMENSIONS SHALL BE TO CENTER UNLESS OTHERWISE SPECIFIED.
ALL DIMENSIONS SHALL BE TO CENTER UNLESS OTHERWISE SPECIFIED.
ALL DIMENSIONS SHALL BE TO CENTER UNLESS OTHERWISE SPECIFIED.
ALL DIMENSIONS SHALL BE TO CENTER UNLESS OTHERWISE SPECIFIED.




CENTEK Engineering
Control of Solutions
2024 441-2105
2024 441-2106
603 1/2 S. Main Street, Pawtucket, RI 02861

| Rev. | Date | Description | Author | Checked | Drawn | Scale |
|------|------------|-------------------|--------|---------|-------|-------|
| 1 | 01/15/2024 | ISSUED FOR BID | | | | |
| 2 | 01/15/2024 | ISSUED FOR PERMIT | | | | |
| 3 | 01/15/2024 | ISSUED FOR ORDER | | | | |


Tectonic
Tectonic Engineering Corporation, Inc.
1370 North 200
Northbrook, IL 60062
Phone: (815) 881-6222
Fax: (815) 881-6221
www.tectoniccorp.com



GROUNDING DETAILS
PROPOSED GUYED TOWER
875 PALMS ROAD
TOWN OF SOUTH KINGSTON
WASHINGTON COUNTY, RI 02882
1/15/2024
10117.01
C301
2



UNIVERSITY OF RHODE ISLAND
SCHOOL OF ENGINEERING
100 SOUTH MAIN STREET
PROVIDENCE, RI 02903
TEL: 401-874-5000
WWW.UR.I/ENGINEERING



CENTEK engineering
Central or Suburban
1725 411-5100
250-684-8277
637-744-8444 (toll-free)

| REV | DATE | DESCRIPTION | BY | CHKD | APP'D |
|-----|----------|--------------------|----|------|-------|
| 1 | 11/11/03 | ISSUED FOR BID | | | |
| 2 | 11/11/03 | ISSUED FOR PERMIT | | | |
| 3 | 11/11/03 | REVISED FOR PERMIT | | | |

Tectonic
ENGINEERING CORPORATION
1000 ROUTE 300
NEWBURGH, NY 10950
PHONE: (845) 887-8888
FAX: (845) 887-8888
WWW.TECTONIC-ENG.COM



GROUNDING DETAILS
PROPOSED QUINN TOWER
370 PLAINS ROAD
TOWN OF SOUTH KINGSTON
WASHINGTON COUNTY, RI 02882
DATE: 12/11/03
PROJECT NO: G508
SHEET NO: 2



NON - MANDATORY PRE-BID CONFERENCE SIGN-IN SHEET

11:18 am

| | | | |
|------------------------|--|----------------------------|----------------|
| BID NUMBER: | 101448 | PURCHASING REPRESENTATIVE: | Andrea Boucher |
| BID TITLE: | Construction of New 400' Radio Tower & Transmitter Building | | |
| LOCATION: | 210 Flagg Road, 1st Floor, Large Conference Room, Kingston, RI 02881 | | |
| PRE BID DATE AND TIME: | 1/10/25 at 11:00 AM | | |

| Company Name: | Representative: | Email Address: | Phone Number |
|--------------------|-----------------|---------------------------------|--------------|
| URI - Purchasing | Andrea Boucher | andrea.boucher@uri.edu | 401-874-9133 |
| PATRIOT TOWERS INC | SHAWN SIMMONS | RFP@PATRIOTTOWERS.COM | 505.889.3391 |
| PNS/Pyramid | Mike D. Mondak | mdmondak@pyramidas.com | 518 366-5679 |
| TECTONIC EPC | GREG LANEY | g.laney@tectonicengineering.com | 914 475-4950 |
| Ew Burman | Joshua Maniz | Estimations@ewburman.com | 401-738-5400 |
| URI - OCP | Kyle Coleman | Kyc Coleman@uri.edu | 617 855 9530 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |